



Alder Residency Private Limited

101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

GST Regn No : 27AAHCA1405F1Z6

OUR VALUES: BUSINESS ETHICS. QUALITY. PRUDENCE. HUMILITY. RESPECT. PRIDE

SERVICE ORDER (Trial Print)

MR RAJAN DUBEY (DIRECTOR) of H. N. POWER SOLUTIONS PRIVATE LIMITED(211530) Address : 111, SWASTIK PLATINUM, NANDIVALI, MALANG GAD ROAD, THANE Thane 421306 Maharashtra India Telephone No. : Fax No. : Mob. : 9833366785 Email : hnpowersolutions@gmail.com PAN No. : AAHCH3594E GST No. : 27AAHCH3594E1ZF Amend.Version :	OrderNo/Date : 3200064035 / 08.05.2025 Plant Code : 1701 Project & Add : KALPATARU VIVANT : (Place of delivery of goods and services) : SURVEY NO 57,58 & 59, HISSA NO 1, 3 & 4, CTS NO 33A, 62 & 76, JVL R MAJASWADI, JOGESHWARI EAST MUMBAI 400060 Payment terms : 97% in 30 days, 3% Retention money
--	--

Pur. Officer : CON-SULEKHA RANE(336)

Subject : Podium / Non-Tower Area Electrical Works including Inst. of Panels, Supply & Inst. of Cable Trays, Cables, Light/power Wiring, earthings, Misc etc. at North Plot, Kalpataru Vivant, Jogeshwari(E).

Dear Sir,

Further to the quote submitted for subject work and rates negotiated and the final offer submitted, we are pleased to issue you service order for Installation of Panels, SI Cable Trays, Cables, Light/power Wiring, earthings, Misc etc. at Kalpataru Vivant, Jogeshwari (E) on the following terms & conditions, Technical Specifications, Tender Drawing.

However, in case of contradiction between the provisions of documents, the latest document shall supersede the previous one and provision of latest document shall be applicable.

1. SCOPE OF WORK:

The scope of work shall be as follows : -

Installation of Panels, SI Cable Trays, Cables, Light/power Wiring, earthings, Misc etc shall comprise of as given below but not limited to:

Supply, Installation, testing & commissioning of switchgears (sheet steel enclosed) inclusive of cable end boxes as required including connection to the other adjoining items.

Installation, testing & commissioning of electrical panels.

Supply, Installation, testing & commissioning of MCB DBs inclusive of fixing in position all switchgears including providing coppers lugs, ferrules, PVC sleeves, cable tie etc.

Providing, laying and jointing all conduit work including point/circuit wiring including wiring accessories like ceiling rose, holder, round acrylic plate, fan hook box with fan hook & PVC cover.

Installation, testing & commissioning of Switches, Sockets, Cover Plates (Inner & Outer).

Providing, Laying, Jointing, Testing & Commissioning cables (Except FS Cables) (on cable tray / wall with saddle) including providing cable end termination.

Installation, testing & commissioning of light fixtures.

Providing & Fixing Cable trays, hangers, supports, and fabrication works.



Alder Residency Private Limited

101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Earthing System.

Providing documents for Liasioning work for getting statutory approval for electrical distribution scheme / layout & installation.

Preparation of Shop Drawings and getting it approved from the Company.

Preparation and submission of As-built Drawings.

The general character and the scope of works to be carried out under this contract is illustrated in Drawings, Specifications and Bill of Quantities. The Contractor shall carry out and complete the said work under this contract in every respect in conformity with the contract documents and with the direction of and to the satisfaction of the Company's site representative.

The contractor shall furnish all labour, material, tools & tackles, temporary work, water, electricity, safety equipment, scaffolding etc, contribution towards employees benefits, labour statutory compliance and every cost & expense towards liabilities, obligation and risk arising out of condition of contract necessary for the proper and successful completion of the works in conformity with the bill of quantities, approved shop drawing and best engineering & construction practices. This also includes any material, equipment, appliances and incidental work not specifically mentioned herein or noted on the drawing/documents as being furnished or installed, but which are necessary and customary to be performed under this contract.

The work will be executed according to the approved shop drawings released from time to time by the Engineer-in-charge progressively during execution of work and according to any additions / modifications / alterations / deletions made from time to time during execution of work.

2. TYPE OF CONTRACT:

The contract shall be re-measured Item Rate Contract. The contract item rate shall be for the complete execution of the item as a whole as detailed in the Bill of Quantities and shall inclusive of supply of all material (except those to be supplied free of cost), labour, all tools & tackles, temporary work etc. required for completion of work, scaffolding, statutory compliance, contribution towards employees benefits and every cost and expense necessary for the proper and successful completion of the works in conformity with the contract documents and best engineering and construction practices. This shall also include repair / maintenance of any work within scope of this contract during the Defects Liability Period.

3. PERFORMANCE BOND: Not Applicable

5% of contract amount in the form of Bank Guarantee OR equivalent amount to be hold from 1st Three RA Bills. Same to be released alongwith final bill amount.

4. MOBILISATION ADVANCE: Not Applicable

Upto 10% of Contract Value against submission of BG of equivalent value in the company's approved format. Advance paid shall be recovered on pro-rata basis from 2nd Running account bills, full advance shall be recovered by the time 80% of work is completed.

5. SECURED ADVANCE:

Company will consider request of Secured Advance payment calculated as 90% of key material value for Wires, Cables, DB, Switchgear, Cable Tray against delivery of material at site within 15 days post delivery of material at site. Contractor shall be paid secured advance on value of materials delivered at site for incorporation in the works after due certification of Engineer-in-charge.

Contractor will raise the invoice for secured advance and payment shall be paid after 21 days from date of procurement at site as discussed & mutually agreed. The contractor shall produce vouchers, invoices in order to ascertain the value of materials.

The material advance for the materials consumed shall be recovered from next immediate bills of the contractor.

Procurement of materials by contractor shall be with prior concurrence of the Engineer-in-charge regarding utilities requirement of procured materials at any early date. The Engineer-in-charge will ascertain himself before certifying payment that such materials are reasonably required for the works, and properly stored and protected by contractor against any loss and meet the requirements of relevant specifications.

6. RETENTION MONEY:



Alder Residency Private Limited

101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

2.75% of gross certified amount will be deducted from each running bill in cash as retention amount. The same will be released on successful completion of the defects liability period of 24 months. The retention money shall not bear any interest. Release of Retention money against submission of Bank Guarantee of equivalent amount shall be at the discretion of Company.

7. DEFECT LIABILITY PERIOD:

The Period of 24 months from the date of virtual completion shall be termed as Defects Liability Period. During this period on notification of Engineer-in-charge, the Contractor shall be bound to replace and/or rectify and make good all defective materials (except free issue material by Company), items, part or accessory and/or workmanship which arise in the works or come to notice subsequent to the Virtual Completion of works.

If Contractor fail to comply with their duties / obligation during period of Defects Liability Period, Engineer-in-Charge has power to depute any other agencies to replace and/or rectify and make good any defective materials, items, part or accessory and/or workmanship and cost incurred towards same shall be adjusted as per actual plus 10% towards Company's charges towards overhead / supervision charges from contractors withheld retention money.

8. Goods and Service Tax (GST):

Contractor is responsible for payment of GST to respective Government (State & Central) and shall file all necessary returns in compliance with State and Central laws including but not limited to Goods and service tax (GST) whether imposed by Central, State or the Union territory. Contractor shall bear applicable GST, any local taxes or any other levies, tax, duties, Cess, Local Body Tax, levied by State Government or Central Government or any statutory or regulatory body thereof by whatever name called wherever and whichever applicable.

(a) If Company does not receive the GST Input tax credit due to failure of the Contractor for compliance with the GST law or non-payment of GST or on account of any error / omission on the part of the Contractor, then Company is not liable to pay GST amount to Contractor. The Contractor will be liable to compensate the loss of GST, interest and penalty incurred by Company. In case GST has already been paid to Contractor by Company, then Contractor agrees that such amount stands as recovery from him and Company has all rights of recovery including recovery from Contractor in next RA Bill or through his retention amount.

(b) Company reserves right to pay the GST tax amount to Contractor only when the Company has received the credit and the same is confirmed as matched credit as per the GSTN portal.

(c) Contractor will upload the information timely and accurately in GSTR-1 return and Company reserves its right to withhold the GST payment till the details of the said invoice are not uploaded properly in the GST return so as to enable Company to claim the credit.

(d) Contractor should pay GST tax amount to the Government within specified period as mentioned in the statute and ensure that he should not get blacklisted under GST provisions. In the event of Contractor is blacklisted or non-compliant under GST law, Company reserves its right to recover the sum of tax, interest and penalty for any past transaction from the future amounts due from the Contractor. In the event of Contractor being blacklisted and continues to Work with Company then no GST is payable to Contractor until his blacklisting continues.

(e) Contractor should continuously maintain a high GST compliance rating score as per the GST law. If the Contractor fails to maintain a high GST compliance rating score in the opinion of the Company, the Company shall notify the Contractor, calling upon him to improve the rating.

(f) Contractor agrees to issue promptly the credit notes as applicable under the GST Law including but not limited to correction in quantity of Work executed, debits to Contractor on account of appropriate reason, liquidated damages, return of goods, discount, deficiency of goods or services, excess charging. Contractor agrees that such credit notes as co-related with invoice is reflected in the GST returns of his next month. Contractor acknowledges that Company will be liable to pay tax, interest and penalty on account of delay in issue of credit notes or for improper issue of credit notes on his side and agrees to reimburse the applicable tax, interest and penalty imposed on Company for his failure.



Alder Residency Private Limited

101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

(g) Contractor is under an obligation (contractual as well as statutory) to issue the invoices containing all the particulars required under the GST Law and acknowledges that the input tax benefit will be denied to Company if the Contractor does not raise the invoice as per the specified particulars. Contractor agrees to reimburse the applicable input tax credit, GST tax, interest and penalty for its failure on this account.

(h) If the Contractor is unregistered under GST, Company reserves its right to pay the GST under reverse charge and Contractor agrees not to charge any GST to Company for such supplies. If the price is inclusive of GST then Company reserves its right to deduct GST from agreed contract price.

(i) Contractor agrees that all the GST benefits arising on account of reduction in rates of goods/services or increased input credits will be passed on by way of reduction of price to Company. Company reserve the right to audit the Contractor books of accounts for the verification of benefits or alternatively, Company can appoint a mutually acceptable practicing Chartered Accountant for the aforementioned Work.

(j) Contractor will ensure that all input tax credit of GST paid by him on Inputs, Capital Goods, Services etc. is availed by him and the same is not considered as cost while quoting the contract price and Contractor will ensure that the benefit of input tax credit is reflected as reduction in price to Company.

(k) In the event of introduction of any new taxing legislation or any change, modification or amendment to any existing tax structure/indirect tax laws in India, rules or regulations, which become effective after execution of contract and results in increase / decrease tax liability for the Contractor, the difference in tax liability shall become payable / deductible to the Contractor subject to production of original documentary proof to the satisfaction of the Company to the extent directly attributable to such changes/amendments in the tax laws in India. The increased cost and/or reduced cost as mentioned above would mean net tax cost which is determined after considering all set-offs and credit available to the Contractor on the goods and services procured by it. Such adjustments / payments by one party to the other, of any increase or decrease of cost defined above shall be made within 3 (three) months of such law coming into force.

9. CONTRACT SUM:

The Contract Sum for Electrical Works of All towers Common Area based on bill of quantities is Rs.1,52,10,284/- (Rupees One Crore Fifty Two Lakhs Ten Thousand Two Hundred & Eighty Four Only). Contract Sum mentioned is inclusive of all applicable taxes, duties, local tax, royalty, transportation, unloading, shifting for all leads & lifts and placing at site etc. including your over head & profit and every cost and expense necessary for the proper and successful completion of the works in conformity with the contract documents and best engineering and construction practices. Only GST (Goods & Service Tax) will be paid separately as per prevailing norms. Labour cess @ 1% will be paid by the Company to the concerned government authorities.

10. CONTRACT DURATION:

The entire scope of works shall be virtually completed within 11(Eleven) months from the date of commencement of work.

Time limits stated above shall be the essence of the contract. Contractor shall complete the works in all respect within the time schedule, subject to any adjustment granted in writing by the Engineer-in-charge under the terms of Contract.

11. TERMS OF PAYMENT:

Unless otherwise provided in the contract and subject to these conditions, the Contractor shall from time to time and in the manner set forth hereunder be entitled to receive payment from Employer for the actual work carried out by him and as approved and certified by the Engineer-in-charge, subject to statutory deduction. The Engineer-in-charge's certificate in this regard shall be conclusive and binding on the Contractor. The Engineer-in-charge shall have the right to withhold such certification should the Contractor fail to comply with any stipulation in the contract documents, until such time as the contractor does comply.

Contractor shall submit all running bills in duplicate as per approved format with detail measurement / joint measurement at site for certification.

70% of the billed Value shall be paid as adhoc within 21 Days and balance 20% within 30 days from the date of submission of bill .



Alder Residency Private Limited

101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

10% will be paid against successful completion of Testing and Commissioning.
The interim bills shall be submitted on monthly basis.

The Contractor shall submit final bill within six weeks after the date of virtual completion of the works,
Final bill payments shall be made within 60 days from date of certification of bill at site.

12. BASIC RATE MATERIAL:

Wires, Cables (Separate Annexure)

The basic rate mentioned in Attachment-1 are landed cost of materials at site inclusive of all taxes, duties and loading except GST. Unloading and Freight charges are considered in the overall rates. These basic rates are considering 30 (thirty) days credit to Contractor from the date of delivery of material at site. In the event of increase / decrease in the price of material procured, the difference in cost shall become payable/deductible after adjustment of input tax setoff. Such adjustment of the rate shall be done based on the quantity of material consumed in the work and rates as per material invoices submitted for assessment of basic rate reimbursement claim. Only the net difference in price shall be considered for adjustment in prices and there shall be no additions on account of labour, wastage, overhead & profits or any other factors.

Contractor has to take prior approval of rates from Employer well in advance before proceeding with procurement of basic rate material. Employer reserves the right to finalize the rates of basic rate materials from their approved vendor, if there is a large variation in the procurement rates of contractor. However, it shall be responsibility of contractor to place an order with the employer approved vendor, receive the materials at site, unload, and stack properly & separately in his stores, making payment to employer approved vendor as per finalized payment terms, testing of material in outside laboratory etc.

The Basic Rate Difference statement to be submitted every month. Contractor has to provide invoice, purchase order, challans to ascertain the rates and quantity of material procured for payment of basic rate reimbursement.

The procurement of materials, identified and whose basic rates has been specified above, shall be done in consultation with the Company. The Contractor shall submit minimum 3(three) quotations and take the approval for a rate, prior to procurement of such materials. Company reserves the right to finalise the rates of all basic rate materials from their approved vendor, if there is a large variation in the procurement rates of contractor. However, it shall be responsibility of contractor to place an order with the Company approved vendor, receive the materials at site, unload, and stack properly & separately in his stores, making payment to Company approved vendor as per finalized payment terms, testing of material in outside laboratory etc. Payment terms of approved vendor to be honoured by contractor. The Company shall pay or recover the difference between the specified basic rate and the procurement rate for a credit period of 30 (thirty) days. In case the Contractor wants to avail credit for a longer period, then the Company shall take into account the procurement rate for a credit period of 30(thirty) days as the rate valid for payment /recovery of the said difference.

13. MATERIAL SUPPLY :

a) Company Supplied Materials - Free of Cost :

Panels, Switches, Sockets and Cover Plates, Light Fixtures, Exhaust Fan, Motion Sensors, Cables FS, UPS, Civil Material (Cement, Sand).

b) Contractor: All materials (except the Free Issue materials) required to complete the scope of work as specified in BOQ shall be brought by Contractor. Contractor shall take Company's Representative (CR) approval for materials brought by him before using them in site.

Permissible Wastage for Free Issue materials - Nil

14 RATE VALIDITY:

The period of price validity is shall be 2 Years from March'2025. During this period the price shall remain firm and contractor shall not be entitled to claim any price escalation on account of material, fuel, Labour etc, except price variation for the Basic Rate materials.

15. Variation in Quantities :-

The Company reserves the right to delete any item of Bill of Quantities from Contractor's Scope of Work



Alder Residency Private Limited

101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

and / or carry it out through other agencies. Also, the Company has right to reduce or increase quantity of any item in Bills of Quantities to any extent. The rates quoted by Contractor in Bill of Quantities for all the items will remain valid despite of deletion / addition of quantity of item as mentioned above.

16. Water and Electricity:

The Company will provide water free of cost to the contractor for construction purpose at one point. Further tapping shall be done by the contractor at the contractor's own cost. Electricity for construction purpose will be provided to the contractor by the Company at free of cost at one point. Further tapping shall be done by the contractor at the contractor's own cost. Drinking Water & electricity for labor accommodation will be in the contractor's scope.

17. Mode of Measurement:

The work shall be measured as per Company's Mode of Measurement Manual Edition 1 - August 2018. If for a particular item of work, the mode of measurement is not given in the Bill of quantities or Mode of Measurement manual, then such work shall be measured as per latest edition of relevant Indian Standards or as mentioned in the BOQ.

18. Extra Items:

The contractor will follow the procedure laid down below to avoid delay in claiming and settling extra items / claims for items not included in Contracts / Work Orders.

Any extra items executed during the course of the month should be given in writing to the GM/ Site in Charge latest by the 30th of the following month with a copy to the concerned coordinating Engineer from the Contracts Department.

- do - as above for compensation / claims if any.

Kindly note that any extra item / claim which are not submitted in writing by the 30th of next month may not be entertained.

Rates of extra items shall be decided on the following basis:

Actual cost of material + labor + 15% towards overheads and profits.

19. Dispute Resolution:

Any claim, dispute or differences concerning the validity and interpretation, implementation or alleged breach of any provision of this Service Order or termination of this Service Order shall be resolved through mutual discussion between the parties hereto, failing which the same shall be referred to and finally resolved by arbitration to be conducted in accordance with the provisions of the Indian Arbitration and Conciliation (Amendment) Act, 2015, as amended. The arbitration panel shall consist of a sole arbitrator to be appointed by mutual agreement of the disputing parties, and failing such agreement, in accordance with the Indian Arbitration and Conciliation (Amendment) Act, 2015, as amended. The arbitration proceedings shall be held in Mumbai and shall be conducted in the English language. The award rendered by the arbitration panel shall be final, conclusive and binding on all parties to this Agreement and shall be subject to enforcement in any court of competent jurisdiction. Each party shall bear the cost of preparing and presenting its case, and the cost of arbitration, including fees and expenses of the arbitrators, shall be shared equally by the disputing parties, unless the award otherwise provides. This clause shall survive the termination of this agreement. This agreement will be governed by and construed in accordance with the laws of India and shall be subject to the exclusive jurisdiction of the Courts at Mumbai only. This clause shall survive the termination of this agreement.

20. Delay & Liquidity Damages:

If the contractor fail to complete the Works within the time stipulated or within any period of authorized extension thereof, then it is agreed that the contractor shall pay to the Company, as fixed liquidated damages and not as a penalty, an amount equivalent to 0.5% of Contract sum for every week of such delay subject to maximum limit of 5% of Contract sum. The Company may, without prejudice to any other method of recovery, deduct the amount of such fixed liquidated damages from any amount in his hands due or which may become due to the contractor. The deduction of such fixed liquidated damages shall not relieve the contractor from the contractor's obligation & liabilities under the Contract.

21. Defective Works:

The Contractor must execute the Work with good quality, as per approved specifications and Site



Alder Residency Private Limited

101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

instructions. The Contractor must not compromise on quality in order to achieve speed. Contractor shall be solely responsible for the defective Works carried out by him and shall bear the cost of the materials and labour for correcting the defects and making good as directed by the Company's CR. If Company supplies any material to the Contractor for redoing the defective Works, the cost for the same shall be recovered at the prevailing price + 10% towards incidental costs. The Contractor shall be responsible for any damage to the building elements during the progress of Work owing to his negligence and shall make good any loss or damage. For all delays in the programme or damage to the Company's reputation caused due to the above reasons, Company reserves the right to impose appropriate penalty to the Contractor's account.

22. Labour, Personnel And Work Rules:

Contractor shall employ only competent and skilled personnel to perform the Work and shall remove from the Work any Contractor personnel determined to be unfit or to be acting in violation of any provision of this Work Order. Contractor is responsible for maintaining labour relations in such manner that there is harmony among Workers and shall comply with and enforce Project and Site procedures, regulations, Work rules, and Work hours established by Company.

Company may at its sole discretion, deny access to the Job Site to any individual by written notice to Contractor. In the event an employee is excluded from the Site, Contractor shall promptly replace such individual with another who is fully competent and skilled to perform the Work.

The Contractor shall comply with all applicable labour laws and shall indemnify and hold harmless the Company against any loss, claim, damages, expenses, suits and proceedings arising out of or incurred by the Company. As a result of any personnel employed or engaged by the Contractor being considered an employee of the Company.

In case Company becomes liable to pay any wages or dues to the labour or to any government agency under the provisions of any Applicable Laws including but not limited to the Minimum Wages Act, 1948; Workmen's Compensation Act, 1923; Contract Labour (Regulation and Abolition) Act, 1970; due to an act or omission by Contractor, Company may make such payments and the total amount of such payments shall be deducted from amounts due or which may become due to Contractor.

23. Workmen Compensation Policy :

The Contract Price shall be deemed to have included the full compensations for all his workmen, Sub-Contractors, Consultants or any other agencies, the Contractor may engage to execute the Work. The Contractor shall indemnify and hold harmless the Company / Site In-charge from and against any claim, costs, demand, expenses, liability arising out of or in connection with any non-compliance of the labour regulations by the Contractor including but not limited claims in relation to payment for wages, salaries, compensations or reimbursements of all nature whether for personal ailment, disabilities both temporary and permanent, injuries or death. The Contractor shall be solely responsible for and shall pay compensation to his workmen payable under the Workmen Compensation Act 1923 (VIII of 1923), (hereinafter called the said Act") for injuries caused to the workmen. If such compensation is payable by the Company as principal company under sub-section (1) of section 12 of the said Act on behalf of the Contractor, such compensation shall be recoverable and/ or adjusted by the Company from the dues payable to the Contractor under sub-section (2) of the said section.

24. STATUTORY COMPLIANCES:

(a) Contractors CAR Policy: Not Applicable

(b) PF/ESIC registration / Workmen Compensation Policy:

The contractor will take PF/ESIC registration / Workmen Compensation Policy within 7 days of receipt of this Service order till completion

of Project duration and submit the respective copies to project Site prior to start of Work.

Certified copies of such policies will be lodged in the Site office.

Contractor to submit PF paid challans copy along with R.A. bills on monthly basis or as per mutually agreed with CR

(c) INSURANCE UNDER WORKMEN COMPENSATION ACT:

Contractor is required to take adequate insurance cover for the labourers under the Workman Compensation Act, 1923 amended from time to time from an approved insurance company and pay premium charges thereof at his own cost. Wherever required by Company the contractor shall produce



Alder Residency Private Limited

101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

the policy or the policies of Insurance and the receipt of payment of the current premiums.

25. Anti-Bribery :-

a) The Supplier/Contractor/Consultant shall comply with the applicable laws of India relating to anti-corruption or anti-bribery, including, but not limited to Prevention of Corruption Act, 1988, Indian Penal Code 1860, Prevention of Money Laundering Act, 2002, Central Vigilance Commission Act, 2003, Lokayukta Acts of various states, etc. (Anti-Bribery Laws). The Supplier/Contractor/Consultant nor any of its affiliates shall make, offer or authorize any payment, gift, promise or other advantage, whether directly or indirectly to any directors, employees, retainers, associates, consultants of the Company, whether working for or engaged by the Company.

b) The Supplier/Contractor/Consultant further represents that no family member or close relative of any of the senior management personnel or any other officer of the Company associated with this PO/WO/Agreement is employed with the Supplier/Contractor/Consultant at present and thus there is no conflict of interest. The Supplier/Contractor/Consultant must at all times implement adequate procedures and practices designed to prevent bribery and corruption and take steps in preventing any activity which would constitute an offence under Anti-Bribery Laws and shall keep detailed up-to-date books, accounts accurately reflecting its transaction relating to this PO/ Agreement and such record shall be retained for a period of not less than six years after their creation.

c) Breach of this clause or of any Anti-Bribery Laws shall constitute a material breach of this PO/WO/Agreement. The decision of the Company on whether the Supplier/Contractor/Consultant has committed such material breach shall be final and binding on the Supplier/Contractor/Consultant. Upon such material breach, without prejudice to any other right, relief or remedy, the Company shall be entitled to terminate this PO/WO/Agreement immediately, without any liability to pay compensation for such termination.

26. Safety Requirements at Site:

The contractor should take adequate precautions for safety at Site by providing Safety Helmets, Safety Belts, safety gloves, goggles etc. to workmen while working / movements at Site. All Electrical lines, temporary / permanent at site should be checked before usage to ensure safety of workmen. If any accident occurs at site due to negligence of the above mentioned safety norms, the contractor will be solely responsible for all the consequences arising out of the above and the company is absolved of any claims / compensation if any payable by the contractor to the contractor's workmen. The contractor should adhere to Agile Real Estate Private Limited's EHS policy, copy of the policy is available at site.

26.1 The contractor shall also abide by the following:

26.1.i. The contractor shall provide required training, PPE and other infrastructure to ensure Covid-19 safety parameters are adhered to.

26.1.ii. Contractors shall update their safety induction, orientation and regular training program to include topic of Covid-19 safety for construction workers.

26.1.iii. Covid-19 safety training shall be conducted at pre-defined levels.

27.Safety of Materials:

The contractor shall provide proper and adequate storage facility to protect all the materials and items including those issued by the Company, against damage from any cause whatsoever. The contractor shall make arrangements at no cost to the Company to replace any item, part or accessory damaged by the contractor or Workmen, employees or agent due to any wilful act, omission, negligence on their part irrespective of the settlement of the Insurance claims.

28. Housekeeping:

The contractor will depute required male coolie throughout the Contract period for cleaning the Site for Work executed & labor camp. If at any time the area where the contractor is Working is found to be unclean, then Company reserves the right to get it cleared through some other agency & debit the cost + 20% extra towards companys overhead and supervision to the contractor's account.

29. Indemnity:

The contractor promise and agree to hereby indemnify and hold us indemnified from and against all



Alder Residency Private Limited

101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

costs, losses, expenses and damages suffered and incurred by us as a direct or indirect result of the contractor's failure to perform or discharge their obligations and responsibilities or the acts or omissions of any of the contractor's sub-Contractors, agent or representatives. This clause shall survive the Termination clause.

30. Withholding the Payments:

The Engineer in charge may withhold payments or, on account subsequently discovered evidence, nullify the whole or a part of any payment certificate to such extent as may be necessary to protect the Company from loss on account of the following:

- a) Defective work not remedied by the Contractor.
- b) Failure of the Contractor to execute the works in conformity with the Contract Documents.
- c) Failure of the Contractor to meet or keep-up the approved construction programme.
- d) Failure of the Contractor to comply with and fulfill all contractual obligations and liabilities stipulated in the Contract Documents.

31. Price Variation : NA

32. SPACE FOR CONTRACTOR'S OFFICE, LABOUR CAMP & STORE:

Contractor will be allotted space depending on the availability free of cost within the Site by the Company to enable the Contractor to construct his office, stores/ godown etc and labour camp. The location, size and other details of the space to be allotted shall be decided by the CR. The Contractor shall accommodate his stores, office within allotted space including construction of office, stores & other infrastructures required for them and do the needful to secure the area at his own expenses. Contractor will use only slotted angles & new GI sheet for constructing stores & offices, as approved by CR. All the establishment of Contractors like their Site office, stores, laboratory, godown, labour camps, toilets and other facilities and temporary Works and arrangements should be removed and the area/location thus occupied should be cleaned and handed over to Company, within 7 days of final bill certificate or earlier as deemed necessary by CR. CR may instruct the Contractor to hand over these areas in part or in whole.

33. ISO Formalities:

Since the Site is following ISO 9001:2008 Quality Management system, the Contractor shall ascertain and understand the details from the Site and follow all the procedures / formalities / approvals required to maintain the system at no extra cost to the Company. Contractor shall implement quality app introduced by Company without any additional cost and time.

34. Risk Purchase Clause:

If the given job is not completed in given time or lacking in quality and finish, then the same Work shall be carried out by the Company and the cost of such rectification of finishes + 15 % incidental cost will be debited to the Contractor from his bills.

35. Site Familiarity:

It is agreed that the Contractor have understood the Site and are aware of and have become acquainted to all the conditions thereof, and have therefore taken into account all the factors into consideration and arrived at conclusion to complete the Work within a stipulated target time. The Contractor have also considered the proximity of the Work and therefore any Work required to be carried out which is not described in the schedule of the Work, so as to enable the Contractor to carry out the Work under Tender, the Contractor have deemed to have taken into consideration the cost of such incidental Work and the same has been appropriately reflected in the pricing of this Tender.

36. Sufficiency of Offer:

It is expressly understood that Contractor's representatives have visited the Site(s) of Work and have acquainted the Contractor to the conditions thereof. It is also expressly understood that the Contractor have taken into account all factors for completing the Works as per the Bill of quantities, in all respects while fixing the rates for different items.

37. ISO Formalities:

Since the site is following ISO 9001:2008 Quality Management system, the contractor shall ascertain and understand the details from the site and follow all the procedures / formalities / approvals required to



Alder Residency Private Limited

101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

maintain the system at no extra cost to the Company. The Contractor shall implement quality app introduced by the Company without any additional cost and time.

38.Storage of Materials:

a) Storage area / room shall be provided to the contractor for storing the materials issued by Company if applicable; however, safety of these materials is in the contractor's scope. The contractor will shift the contractor's storage area if need arises without any extra cost to the Company.

b) The contractor shall shift the contractor r storage area at any lead if need arises without any extra cost of the Company.

c) Material brought by the contractor at Site should be shifted to the contractor's godown given by the Company within one day.

d) Challan copy of Details of materials received to be submitted to company on monthly basis with security entry stamp.

39. Co-ordination with other Contractors and Agencies:

During the execution of the Works the contractor's shall co-ordinate with other Contractors and other agencies associated with the project and shall Work in harmony with them without causing any hindrance or obstruction to the progress of their Work in any way. In respect of the Work of other Contractors and agencies, where the commencement or progress of such Work of any other Contractor, or agency, is dependent upon the completion of particular portions of the Contractor Work or generally upon the Contractor maintaining progress in accordance with the approved coordinated construction Programme, it shall be the contractor r responsibility to complete with such portions and maintain such progress.

40. Quality rating should adhere to Kalpataru requirements. During SES entry in SAP, these rating should be made clear in presence of the contractor r representative.

41. FORCE MAJEURE

A) An event of Force Majeure means an event or combination of events or circumstances beyond the control of the Company and / or the Contractor which cannot by - 1. Exercise of reasonable diligence, or 2. Despite the adoption of reasonable precaution and / or alternative measures, be prevented or caused to be prevented, makes it impossible or illegal to perform and which adversely affects the Company's and / or the Contractor's ability to perform under this Agreement, which shall include - but not limited to - acts, events and circumstances, such as

(i) act of war (whether declared or undeclared), invasion, armed conflict or act of foreign enemy, blockade, embargo, revolution, riot insurrection, civil commotion, act of terrorism or sabotage, in each case occurring anywhere but impacting the Company's and / or the Contractor's obligation under this Agreement and affecting the Company and / or Contractor in any way (the impact of which shall be determined solely at the discretion of the Company);

(ii) strikes, lockouts or other generalized labour action occurring throughout the Industry / country as a whole within India and affecting the Company and / or Contractor directly; (iii) Radioactive contamination or ionizing radiation or chemical contamination originating from a source in India and affecting the Company and / or Contractor directly or resulting from another Force Majeure Event; (i.e.) flood, cyclone, lightning, earthquake, drought, storm or any other extreme effect of the natural elements and affecting the Company and / or the Contractor's work directly;

(iv) epidemic and / or pandemic and / or plague, affecting the Company and / or Contractor directly;

(v) fire and / or explosion, affecting Company and / or Contractor directly except as may be attributable to the Contractor;

(vi) air crash and / or shipwreck which affects Company's and / or Contractor's work directly;

(vii) an act of God (the definition of which shall be decided by the Company, and the same shall be final and binding);

(Viii) Act of Government;

(ix) Change and / or amendment and / or restrictions imposed on the applicability in Law(s) pertaining to laws of the Republic of India.

B) If the effect of any events specified in above clause lasts for a continuous period of less than three (3) days, such events shall not be construed to be Force Majeure Events. However, the after-effects of such event(s) shall be considered to be construed as Force Majeure, which shall be decided by the sole



Alder Residency Private Limited

101, KALPATARU SYNERGY, OPP. GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055, Maharashtra

discretion of the Company.

C) If the effect(s) of any event(s) specified in above clause occurs sporadically for longer period of time but independently occurs for periods less than three (03) days, such events shall also be construed to be Force Majeure, and the end or culmination of the Force Majeure shall be decided solely by the Company.

42. EFFECT OF FORCE MAJEURE & OBLIGATION OF THE PARTIES

A) In the event of Force Majeure, No Party shall be responsible to the other Party for delay or failure in performance of any of its obligations under this Agreement, if such delay or failure is occasioned by a Force Majeure event;

B) In case the Force Majeure event occurs during the Company's delay or failure in performance of any of its obligations under this Agreement, then the such (existing and / or ongoing) delay or failure of the Company shall become null and void, and the Contractor shall hold the Company harmless in this regards;

C) There shall be no termination of the Contract except as provided in the Termination Clause;

D) A reasonable Extension of Time (EOT) shall be accorded to the Contractor by the Company. For sake of clarity, EOT shall be purely an extension to the Time for Completion and the Contractor shall not be eligible to any costs (direct, indirect or otherwise), and the Price Validity Period shall also be proportionately extended accordingly;

E) The Milestones and the Time for Completion shall be extended either individually to a phase and / or tower, or to the entire Time for Completion of the all the Phases and / or Towers as a whole. This EOT shall be either "interim" or "final" in nature, and at the discretion of the Company, and the Contractor shall hold the Company harmless against any claims in this regards;

F) Liquidated Damages - The Company shall reserve the right to alter the way in which the Liquidated Damages will be imposed - viz. Liquidated Damages may be altered to be imposed on each phase and / or tower, and / or the project as a whole - and the Contractor shall hold the Company harmless in this regards;

G) Should the Time for Completion expire during the Force Majeure event or should have expired just prior to the occurrence of the Force Majeure event, the Company shall accord an EOT either for the full duration of the Force Majeure event (in case the Time for Completion has expired before the occurrence of the Force Majeure event), or a partial EOT (for part of the Force Majeure event occurring beyond the expiry of the Time for Completion) - in either case, the decision of the Company shall be final and binding, and the Contractor shall hold the Company harmless in this regards;

H) During and / or after the Force Majeure, the Company shall not be obliged to pay any kind of ex-gratia to the Contractor for whatsoever reasons, including but not limited to direct costs, indirect costs, etc. The Company reserves the right to renegotiate the rates and / or the terms and conditions of this Agreement, should the Company feel that the prevailing circumstances necessitate the need to do so, and the Contractor shall oblige to the same without any objection(s) and carry-out the Contractor's obligation(s) under this Agreement and / or any revised Agreement(s) thereof;

I) In case the Force Majeure has occurred during the Defects Liability Period (DLP), the Company shall extend the duration of such DLP as deemed necessary and the Contractor shall hold the Company harmless against any claims in this regards.

43. Termination of Contract by the Company :

a) If at any time during the execution of contract, the Company shall for any reason whatsoever, other than the default on the part of contractor, desire that the whole or any part of the work specified in the contract should be suspended for any period or the whole or part of the work should not be carried out at all, he shall give the contractor a notice in writing of such desire and upon receipt of such notice the contractor shall immediately suspend or stop the work wholly or in part as required after having due regard to the appropriate stage at which the work should be stopped or suspended so as not to cause any damage or injury to the work already done.

b) The contractor should have no claim to any payment or compensation whatsoever by reason of or in pursuance of any notice as aforesaid, on account of any suspension, stoppage or curtailment except to the extent of work done up to the time of such suspension of work.

c) In case, the work is suspended for more than 120 days at the instance of the Company, then the contractor shall be entitled only for an extension of time for an equivalent time period.

d) If the Contractor fails to carry out any of his obligation, or if the Contractor has not executed the works



Alder Residency Private Limited

101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

in accordance with the contract, the Project Engineer-in-charge may give 15 days notice to the Contractor requiring him to make good such failure and remedy the same.

e) If the Contractor -

- i) Fails to comply with a notice under sub clause (d);
- ii) Abandons or repudiates the contract or;
- iii) Without reasonable excuses fails to proceed with the works in accordance with the technical specifications and to demonstrate that sufficient design capability is employed in the design of the works or;
- iv) Persistently fails to supply sufficient skilled superintendent and workmen or suitable materials or equipment or;
- v) Persistently fails to make prompt payments to sub-contractors or for labour, materials or equipment or;
- vi) Disregards laws, ordinances, rules, regulations, or orders of any public body having jurisdiction or;
- vii) Fails to comply with statutory requirements or;
- viii) Violates any provisions of the contract or;
- ix) Disregards the authority of the Company or neglects to execute the work in accordance with the contract documents or;
- x) Disregards commitments given to achieve the required progress as per the agreed schedule or;
- xi) Willfully executes the work in bad faith or;
- xii) Becomes bankrupt or insolvent, goes into liquidation, has a receiving or administration order made against him, compound with his creditors, or carries on business under a receiver, trustee or manager for the benefit of his creditors, or if any act is done or event occurs which has a similar effect to any of these acts or events, or;
- xiii) Assigns the contract or subcontract the works without the required consent.

Then the Company may, without prejudice to any of their right or remedy and by means of written notice sought explanation from the contractor within 14 days, why the said contract should not be terminated.

On receiving the reply from the contractor, the Company may terminate the contract.

The Contractor shall then deliver all relevant documents, and other design documents made by or for him, to the EIC.

The Company may upon such termination complete the works by any other Contractor. The Company shall be entitled to recover from the Contractor the extra costs, if any, of completing the works.

44. Notice and Communication:-

1. Any notice, communication, request, instruction or other documents to be given hereunder by any party to the other will be in writing addressed to the Project in charge or from the Project in charge and shall be deemed effectively given upon personal delivery at the below mentioned addresses:

1.1. Employer

Project in Charge

Contact Person : Mr.Sunil Jadhav

Address :

M/s. Alder Residency Pvt Ltd.

JVLR, Jogeshwari, Mumbai

E-mail : Sunil.Jadhav2@kalpataru.com

1.2. Contractor

Contact Person : Mr Rajan Dubey

Address :

111, Swastik Platinum,

Nandivali, Malang Gad Road,

Kalyan (East) , Thane -421306

Mobile No : 9833366785

E-Mail : hnpowersolutions@gmail.com

2. All formats for communication (letters, submittals, RFIs, etc.) shall be agreed with the Project In Charge within 30 days from Commencement of work at site. Emails shall be deemed effectively only when the hard copies of the same are printed & attached to the agreed format of communication.

45. This Service Order forms a binding Contract between the parties, and the contractor shall commence the Works as per schedule mutually agreed. All other terms & condition tender document will applicable



Alder Residency Private Limited

101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

to this service order.

This order is being sent to the contractor in duplicate. The contractor is requested to sign & stamp and return one copy to us as a token of the contractor's acceptances.

This Order forms a binding Contract between us. The contractor is requested to sign & stamp and return one copy to us as a token of the contractor's acceptance.

This order along with all the annexures contained herein supersedes all previous communication on the subject. Any changes to the same post this Order shall be considered valid only if the same is modified through a suitable amendment to this order issued by the company

Note: Contractor to follow all Terms and conditions as per Safety Guidelines Policy.

"GUIDELINES FOR SAFETY MANAGEMENT AT CONSTRUCTION WORKSITES" read & received.

Enclosures

- 1) Basic Rate list.
- 2) Technical Specifications
- 3) Approved Make List
- 4) EHS Policy Document



Alder Residency Private Limited

101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

BILL OF QUANTITIES :-

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
1	ELECTRICAL PANELS INSTALLATION Installation including Unloading at site, shifting to final location, assembling, leveling, grouting, erecting, testing and commissioning of following panels as per drawings. Any sort of fabrication work required for erection of panel at site shall be done by the contractor. The contractor shall also check for all the loose joints and continuity of the panel. Any physical or technical defects envisaged by the contractor shall be brought to consultants and clients knowledge. All floor mounted panels shall be with 150mm height stand as per site condition. Panel shall include ACB/MCCB / MCB/BUSBAR BOX/TIMER with 16G MS powder coated enclosure, necessary busbar /spreader links, rotary handle etc complete. All MCCB upto and including 500A shall be thermal magnetic adjustable and above 500 A shall be with microprocessor trip units as per SLD.Approval of GA Drawing By Electrical Consultants/Client is must before fabrication. Refer SLD (KL-VIVN-MES-NP-W-E-E-1.3)				
1	1302651 SAC 9954 Supply and Installation of Fire Pump Panel. COMMON AREA PANEL	NO	1.000	30,000.00	30,000.00
2	1303733 SAC 9954 Installation of Fire Pump Panel COMMON AREA PANEL -EMERGENCY	NO	1.000	30,000.00	30,000.00
3	1307940 SAC 9954 Installation of plumbing panel DG PANEL	NO	1.000	25,500.00	25,500.00
4	1302741 SAC 9954 Installation of Panel. PLUMBING PANEL	NO	1.000	25,500.00	25,500.00
5	1309121 SAC 9954 APFC PANEL -55KVAR MCC-FIRE FIGHTING PANEL-1	NO	1.000	26,000.00	26,000.00
6	1301826 SAC 9954 Installation of main D.G. Panel. MCC-FIRE FIGHTING PANEL-2	NO	1.000	26,000.00	26,000.00

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
7	1308586 SAC 9954 SITC of Common Ventilation Panel MAIN VENTILATION PANEL	NO	1.000	25,500.00	25,500.00
8	1300337 SAC 9954 ITC of Lighting Electrical Panel. AMENITY AREA PANEL	NO	1.000	24,500.00	24,500.00
9	1305792 SAC 9954 Emergency panel-1 STACK PARKING PANEL (B1)	NO	1.000	20,500.00	20,500.00
10	1306488 SAC 9954 I of 40KVAR APFCR Panel STACK PARKING PANEL (B2)	NO	1.000	20,500.00	20,500.00
11	1307728 SAC 9954 Main Stack Parking Panel (SPP-M) STP PANEL	NO	1.000	20,500.00	20,500.00
12	1303020 SAC 9954 Installation of power distribution panel 35 KVAR APFC PANEL	NO	3.000	18,500.00	55,500.00
13	1308590 SAC 9954 SITC of 1600A FP ATS Supply & Installation of ACB/MCCB / MCB/BUSBAR BOX/TIMER with 16G MS powder coated enclosure, necessary busbar /spreader links, rotary handle etc complete. All MCCB upto and including 250A shall be thermal magnetic adjustable and above 250 A shall be with microprocessor trip units. Approval of GA Drawing By Electrical Consultants/Client is must before fabrication. Service to be read as : - SITC of 1600A TPN,36kA ACB with M.S. enclosure & busbar complete. (DG panel).	NO	1.000	175,000.00	175,000.00
14	1300409 SAC 9954 ITC of 1000A TPN MCCB Supply & Installation of ACB/MCCB / MCB/BUSBAR BOX/TIMER with 16G MS powder coated enclosure, necessary busbar /spreader links, rotary handle etc complete. All MCCB upto and including 250A shall be thermal magnetic adjustable and above 250 A shall be with microprocessor trip units. Approval of GA Drawing By Electrical Consultants/Client is must before fabrication. Service to be read as : - SITC of 800A TPN,25kA MCCB with	NO	2.000	41,663.00	83,326.00

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
	M.S. enclosure & busbar complete. (Main fire pump).				
15	1309181 SAC 9954 SITC of 320A FP MCCB Supply & Installation of ACB/MCCB / MCB/BUSBAR BOX/TIMER with 16G MS powder coated enclosure, necessary busbar /spreader links, rotary handle etc complete. All MCCB upto and including 250A shall be thermal magnetic adjustable and above 250 A shall be with microprocessor trip units. Approval of GA Drawing By Electrical Consultants/Client is must before fabrication. Service to be read as : - SITC of 300A TPN,25kA MCCB with M.S. enclosure & busbar complete. (Common area panel/Amenity panel).	NO	2.000	12,935.00	25,870.00
16	1301166 SAC 9954 S 250A TPN MCCB Supply & Installation of ACB/MCCB / MCB/BUSBAR BOX/TIMER with 16G MS powder coated enclosure, necessary busbar /spreader links, rotary handle etc complete. All MCCB upto and including 250A shall be thermal magnetic adjustable and above 250 A shall be with microprocessor trip units. Approval of GA Drawing By Electrical Consultants/Client is must before fabrication. Service to be read as : - SITC of 250A TPN,25kA MCCB with M.S. enclosure & busbar complete. (Plumbing panel-1).	NO	1.000	12,800.00	12,800.00
17	1309182 SAC 9954 SITC of 200A FP MCCB Supply & Installation of ACB/MCCB / MCB/BUSBAR BOX/TIMER with 16G MS powder coated enclosure, necessary busbar /spreader links, rotary handle etc complete. All MCCB upto and including 250A shall be thermal magnetic adjustable and above 250 A shall be with microprocessor trip units. Approval of GA Drawing By Electrical Consultants/Client is must before fabrication. Service to be read as : - SITC of 200A TPN,26kA MCCB with M.S. enclosure & busbar complete. (Main ventilation /STP panel).	NO	2.000	14,672.00	29,344.00
18	1307534 SAC 9954 Supply of 80A FP MCB with M.S.	NO	3.000	8,600.00	25,800.00

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
	enclosure Supply & Installation of ACB/MCCB / MCB/BUSBAR BOX/TIMER with 16G MS powder coated enclosure, necessary busbar /spreader links, rotary handle etc complete. All MCCB upto and including 250A shall be thermal magnetic adjustable and above 250 A shall be with microprocessor trip units. Approval of GA Drawing By Electrical Consultants/Client is must before fabrication. Service to be read as : - SITC of 80A TPN,25kA MCCB with M.S. enclosure & busbar complete.				
19	1306388 SAC 9954 63 amp 4 pole MCB Supply & Installation of ACB/MCCB / MCB/BUSBAR BOX/TIMER with 16G MS powder coated enclosure, necessary busbar /spreader links, rotary handle etc complete. All MCCB upto and including 250A shall be thermal magnetic adjustable and above 250 A shall be with microprocessor trip units. Approval of GA Drawing By Electrical Consultants/Client is must before fabrication. Service to be read as : - SITC of 63A TPN,25kA MCCB with M.S. enclosure & busbar complete.	NO	2.000	3,200.00	6,400.00
20	1308719 SAC 9954 SITC 32A FP MCB 10KA Supply & Installation of ACB/MCCB / MCB/BUSBAR BOX/TIMER with 16G MS powder coated enclosure, necessary busbar /spreader links, rotary handle etc complete. All MCCB upto and including 250A shall be thermal magnetic adjustable and above 250 A shall be with microprocessor trip units. Approval of GA Drawing By Electrical Consultants/Client is must before fabrication. Service to be read as : - SITC of 16/32A FPMCB in M.S. enclosure complete.	NO	5.000	2,800.00	14,000.00
21	1308719 SAC 9954 SITC 32A FP MCB 10KA Supply & Installation of ACB/MCCB / MCB/BUSBAR BOX/TIMER with 16G MS powder coated enclosure, necessary busbar /spreader links, rotary handle etc complete. All MCCB upto and including 250A shall be thermal magnetic	NO	100.000	2,800.00	280,000.00

**Alder Residency Private Limited**

101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
	adjustable and above 250 A shall be with microprocessor trip units. Approval of GA Drawing By Electrical Consultants/Client is must before fabrication. Service to be read as : - SITC of 16/32A FPMCB + ELCB 100mA in M.S. enclosure complete.				
22	1308720 SAC 9954 SITC 40A FP MCB 10KA Supply & Installation of ACB/MCCB / MCB/BUSBAR BOX/TIMER with 16G MS powder coated enclosure, necessary busbar /spreader links, rotary handle etc complete. All MCCB upto and including 250A shall be thermal magnetic adjustable and above 250 A shall be with microprocessor trip units. Approval of GA Drawing By Electrical Consultants/Client is must before fabrication. Service to be read as : - SITC of 40 A FP MCB + ELCB, 100ma with enclosure complete.	NO	2.000	3,200.00	6,400.00
23	1308718 SAC 9954 SITC 32A DP MCB 10KA Supply & Installation of ACB/MCCB / MCB/BUSBAR BOX/TIMER with 16G MS powder coated enclosure, necessary busbar /spreader links, rotary handle etc complete. All MCCB upto and including 250A shall be thermal magnetic adjustable and above 250 A shall be with microprocessor trip units. Approval of GA Drawing By Electrical Consultants/Client is must before fabrication. Service to be read as : - SITC of 32 A DP MCB + ELCB, 100ma with enclosure complete.	NO	5.000	3,200.00	16,000.00
				Subtotal	1,004,940.00
				SGST 9 %	90,444.60
				CGST 9 %	90,444.60

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
2	CABLE TRENCH AND TRAY				
1	1301455 SAC 9954 Providing and Fixing 1200mm wide Prefabricated ladder type G.I.cable tray "Profab" make in following sizes with 10mm G.I. rod,Anchor fasteners and "C" Channel Support. Supply and Erecting Ladder type Hot dip G.I. cable tray of 14G of specific dimensions. The cable tray shall be hung from ceiling / fixed to wall with necessary ceiling suspensors, tee, flat sections, nuts etc, together with tees, bends etc including cost for supports as described. The tray shall be earthed. Min size (not a limitation) of supports shall be as follows (a).-up to 300mm tray 2nos. 8mm full threaded GI rod with 2nos.anchor fastener and "C" channel support at 1250mm distance (b) 450 to 600mm tray 2nos.10mm full treaded GI rod with 2nos. anchor fastener and "C" channel support at 1000mm distance (c) 750 / 1000 mm cable tray with fabrication of 25 x 6 mm angle frame with min. 4 nos anchor fastener at 1000 mm distance. Cable tray Supports shall be of Hot Dip GI. Size : 1200 X 75 mm	RMT	155.000	1,920.00	297,600.00
2	1301454 SAC 9954 Providing and Fixing 1000mm wide Prefabricated ladder type G.I.cable tray "Profab" make in following sizes with 10mm G.I. rod,Anchor fasteners and "C" Channel Support. Supply and Erecting Ladder type Hot dip G.I. cable tray of 14G of specific dimensions. The cable tray shall be hung from ceiling / fixed to wall with necessary ceiling suspensors, tee, flat sections, nuts etc, together with tees, bends etc including cost for supports as described. The tray shall be earthed. Min size (not a limitation) of supports shall be as follows (a).-up to 300mm tray 2nos. 8mm full threaded GI rod with 2nos.anchor fastener and "C" channel support at 1250mm distance (b) 450 to 600mm tray 2nos.10mm full treaded GI rod with 2nos. anchor fastener and "C" channel support at 1000mm distance (c) 750 / 1000 mm cable tray with fabrication of 25 x 6 mm angle frame with min. 4 nos anchor fastener at 1000 mm distance. Cable tray Supports shall be of Hot Dip GI. Size : 1000 x 75 mm	RMT	297.000	1,720.00	510,840.00

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
3	1306253 SAC 9954 GI ladder cable tray # 750 mm wide Supply and Erecting Ladder type Hot dip G.I. cable tray of 14G of specific dimensions. The cable tray shall be hung from ceiling / fixed to wall with necessary ceiling suspensors, tee, flat sections, nuts etc, together with tees, bends etc including cost for supports as described. The tray shall be earthed. Min size (not a limitation) of supports shall be as follows (a).-up to 300mm tray 2nos. 8mm full threaded GI rod with 2nos.anchor fastener and "C" channel support at 1250mm distance (b) 450 to 600mm tray 2nos.10mm full treaded GI rod with 2nos. anchor fastener and "C" channel support at 1000mm distance (c) 750 / 1000 mm cable tray with fabrication of 25 x 6 mm angle frame with min. 4 nos anchor fastener at 1000 mm distance. Cable tray Supports shall be of Hot Dip GI. Size : 750 x 50mm	MTR	97.000	1,155.00	112,035.00
4	1301453 SAC 9954 Providing and Fixing 600mm wide Prefabricated ladder type G.I.cable tray "Profab" make in following sizes with 10mm G.I. rod,Anchor fasteners and "C" Channel Support. Supply and Erecting Ladder type Hot dip G.I. cable tray of 14G of specific dimensions. The cable tray shall be hung from ceiling / fixed to wall with necessary ceiling suspensors, tee, flat sections, nuts etc, together with tees, bends etc including cost for supports as described. The tray shall be earthed. Min size (not a limitation) of supports shall be as follows (a).-up to 300mm tray 2nos. 8mm full threaded GI rod with 2nos.anchor fastener and "C" channel support at 1250mm distance (b) 450 to 600mm tray 2nos.10mm full treaded GI rod with 2nos. anchor fastener and "C" channel support at 1000mm distance (c) 750 / 1000 mm cable tray with fabrication of 25 x 6 mm angle frame with min. 4 nos anchor fastener at 1000 mm distance. Cable tray Supports shall be of Hot Dip GI. Size : 600 x 50 mm	RMT	92.000	980.00	90,160.00
5	1306313 SAC 9954 SF GI ladder cable tray # 450 mm wide Supply and Erecting Ladder type Hot dip G.I. cable tray of 14G of specific dimensions. The cable tray shall be hung	MTR	115.000	895.00	102,925.00

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
	from ceiling / fixed to wall with necessary ceiling suspensors, tee, flat sections, nuts etc, together with tees, bends etc including cost for supports as described. The tray shall be earthed. Min size (not a limitation) of supports shall be as follows (a).-up to 300mm tray 2nos. 8mm full threaded GI rod with 2nos.anchor fastener and "C" channel support at 1250mm distance (b) 450 to 600mm tray 2nos.10mm full treaded GI rod with 2nos. anchor fastener and "C" channel support at 1000mm distance (c) 750 / 1000 mm cable tray with fabrication of 25 x 6 mm angle frame with min. 4 nos anchor fastener at 1000 mm distance. Cable tray Supports shall be of Hot Dip GI. Size : 450 x 50 mm				
6	1301452 SAC 9954 Providing and Fixing 300mm wide Prefabricated ladder type G.I.cable tray "Profab" make in following sizes with 10mm G.I. rod,Anchor fasteners and "C" Channel Support. Supply and Erecting Ladder type Hot dip G.I. cable tray of 14G of specific dimensions. The cable tray shall be hung from ceiling / fixed to wall with necessary ceiling suspensors, tee, flat sections, nuts etc, together with tees, bends etc including cost for supports as described. The tray shall be earthed. Min size (not a limitation) of supports shall be as follows (a).-up to 300mm tray 2nos. 8mm full threaded GI rod with 2nos.anchor fastener and "C" channel support at 1250mm distance (b) 450 to 600mm tray 2nos.10mm full treaded GI rod with 2nos. anchor fastener and "C" channel support at 1000mm distance (c) 750 / 1000 mm cable tray with fabrication of 25 x 6 mm angle frame with min. 4 nos anchor fastener at 1000 mm distance. Cable tray Supports shall be of Hot Dip GI. Size : 300 x 50mm	RMT	288.000	1,050.00	302,400.00
7	1306255 SAC 9954 GI perforated cable tray # 300mm wide Supply and Erecting PERFORATED type Hot dip G.I. cable tray of 14G of specific dimensions. The cable tray shall be hung from ceiling / fixed to wall with necessary ceiling suspenders, tee, flat sections, nuts etc, together with tees, bends etc including cost for supports as described. The tray shall be earthed. Min size (not a limitation) of supports shall be as follows	MTR	160.000	1,020.00	163,200.00

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
	(a).-up to 300mm tray 2nos. 8mm full threaded GI rod with 2nos.anchor fastener and "C" channel support at 1000mm distance (b) 450 to 600mm tray 2nos.10mm full treaded GI rod with 2nos. anchor fastener and "C" channel support at 1000mm distance (c) 750 / 1000 mm cable tray with fabrication of 25 x 6 or 50 x 3 mm angle frame with min. 4 nos anchor fastener at 750 mm distance. Cable tray Supports shall be of Hot Dip GI. Size : 300 x 50 mm				
8	1306256 SAC 9954 GI perforated cable tray # 200mm wide Supply and Erecting PERFORATED type Hot dip G.I. cable tray of 14G of specific dimensions. The cable tray shall be hung from ceiling / fixed to wall with necessary ceiling suspenders, tee, flat sections, nuts etc, together with tees, bends etc including cost for supports as described. The tray shall be earthed. Min size (not a limitation) of supports shall be as follows (a).-up to 300mm tray 2nos. 8mm full threaded GI rod with 2nos.anchor fastener and "C" channel support at 1000mm distance (b) 450 to 600mm tray 2nos.10mm full treaded GI rod with 2nos. anchor fastener and "C" channel support at 1000mm distance (c) 750 / 1000 mm cable tray with fabrication of 25 x 6 or 50 x 3 mm angle frame with min. 4 nos anchor fastener at 750 mm distance. Cable tray Supports shall be of Hot Dip GI. Size : 200 x 50mm	MTR	50.000	980.00	49,000.00
9	1306315 SAC 9954 SF GI perforated cable tray # 150mm wide Supply and Erecting PERFORATED type Hot dip G.I. cable tray of 14G of specific dimensions. The cable tray shall be hung from ceiling / fixed to wall with necessary ceiling suspenders, tee, flat sections, nuts etc, together with tees, bends etc including cost for supports as described. The tray shall be earthed. Min size (not a limitation) of supports shall be as follows (a).-up to 300mm tray 2nos. 8mm full threaded GI rod with 2nos.anchor fastener and "C" channel support at 1000mm distance (b) 450 to 600mm tray 2nos.10mm full treaded GI rod with 2nos. anchor fastener and "C" channel support	MTR	188.000	882.00	165,816.00



Alder Residency Private Limited

101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
	at 1000mm distance (c) 750 / 1000 mm cable tray with fabrication of 25 x 6 or 50 x 3 mm angle frame with min. 4 nos anchor fastener at 750 mm distance. Cable tray Supports shall be of Hot Dip GI. Size : 150 x 35 mm				
				Subtotal	1,793,976.00
				SGST 9 %	161,457.84
				CGST 9 %	161,457.84

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
3	DISTRIBUTION BOARDS - FACTORY Supply, Installation, testing and commissioning of distribution boards - readymade concealed or surface on angle support as required (supports included in cost of DB). The DB shall be double door type and vertical in fashion. All Indoor Type DB shall be IP 43 and Outdoor application DB shall be of IP 67. VTPN DB shall be provided with additional cable end boxes for glanding cables and necessary spreader links as per cable size given in SLD for proper termination.				
1	1308392 SAC 9954 12way VTPN DB-switchgear Supply installation testing and commissioning of 12way Vertical Distribution board with 63A FP MCB, 10kA as incomer and 12 nos 32A TP MCB as outgoing.	NO	9.000	25,000.00	225,000.00
2	1307672 SAC 9954 6 Way VTPN DB Supply installation testing and commissioning of 6 way Vertical Distribution board with 63A FP MCB 10kA as incomer and 12 nos 16/25 A SPMCB & 2 nos 25A TPMCB as outgoing.	NO	1.000	13,177.78	13,178.00
3	1308297 SAC 9965 8 way VTPN DB - Switchgears Supply installation testing and commissioning of 8 way Vertical Distribution board with 80A FP MCB, 16KA MCCB as incomer and 2no of 63A TPMCB + 4 nos. of 25/32A TPMCB + 6 nos. of 25A SP MCB as outgoing.	NO	1.000	25,000.00	25,000.00
4	1308723 SAC 9954 SITC 4-WAY VTPN DB Supply installation testing and commissioning of 4 way Vertical Distribution board with 40A FP MCB, 10kA as incomer and 2 nos 25 A TPMCB + 6 nos 25 A SPMCBas outgoing.	NO	1.000	17,158.28	17,158.00
5	1306383 SAC 9954 12 way TPN DB Supply installation testing and commissioning of 12 way double door distribution board with 32A 30mA 4P RCBO as incomer and 36 nos 6-16A SP	NO	5.000	5.00	25.00

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
	MCB + 3 nos 16A DP MCB and 3 nos 0-24 hrs 16A Digital modular timer & 16A DP Contactor on two phases as outgoing. (REF: KL-VIVN-MES-NP-B1-E-1.5) [LPDB-B1, LPDB-B2, LPDB-G (BASEMENT-1, BASEMENT-2 AND GROUND,PODIUUM-1 & 2 PARKING AREAS PARKING AREAS)].				
6	1301833 SAC 9954 Installation of Distribution Board. Supply installation testing and commissioning of 14X3way flexy double door distribution board with 63A 30mA FP RCBO as incomer and 20 nos 6-20A SPMCB, 32A FP MCB [(LPDB GYM (TF) / PARTY HALL (TC) / INDOOR GAMES/CRECHE].	NO	4.000	4.00	16.00
7	1302252 SAC 9954 Supply and installation of DB as per instructed by site in charge etc complete. Supply installation testing and commissioning of 14X3way flexy double door distribution board with 63A 30mA FP RCBO, 25ADP MCB-2nos as incomer and 9 nos 6-20A SPMCB, 25A FP MCB (LPDB YOGA & FITNESS CENTER (TA)/MULTIPURPOSE HALL)]	NO	2.000	19,465.92	38,932.00
8	1308394 SAC 9954 12way TPN DB-switchgear Supply installation testing and commissioning of 12 way double door distribution board with 40A DP RCBO as incomer and 8 nos 6-20A SPMCB- (LPDB FOR LIBRARY)	NO	1.000	9,331.13	9,331.00
9	1306862 SAC 9954 6-Way TPN DB Supply installation testing and commissioning of 6 way double door distribution board with 40A 30mA FP RCCB as incomer, 25A DP MCB-3 Nos and 12 nos 6-16A SPMCB as outgoing. [(LPDB FOR SPA & SAUNA / MINI THEATER(TC)]	NO	2.000	18,619.41	37,239.00
10	1304799 SAC 9954 12 Way TPN DB with MCB as instructed by site incahrge ,etc completed Supply installation testing and commissioning of 12 way double door distribution board with 40A DP RCBO as incomer and 8 nos 6-20A SPMCB, 0-24 hrs 25A Digital modular timer per phase	NO	3.000	15,530.46	46,591.00

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
	as outgoing. (FOR GRD FL-LANDSCAPE)				
11	1304799 SAC 9954 12 Way TPN DB with MCB as instructed by site incharge ,etc completed Supply installation testing and commissioning of 12 way double door distribution board with 63A FP MCB + 63A 30mA FP RCCB as incomer and 24 nos 6-16A SP MCB + 3 nos 25A DP MCB and 3 nos 0-24 hrs 25A Digital modular timer & 25A DP Contactor on two phases as outgoing.[LPDB-LANDSCAPE(AMENITY)]	NO	1.000	15,500.00	15,500.00
12	1302252 SAC 9954 Supply and installation of DB as per instructed by site in charge etc complete. Supply installation testing and commissioning of 14X3way flexy double door distribution board with 63A 30mA FP RCBO as incomer and 20 nos 6-20A SPMCB, 32A FP MCB [(BUSINESS CENTER (TD) / SOCIETY OFC / CONVENIENCE STORE)].	NO	3.000	17,780.36	53,341.00
13	1306382 SAC 9954 8 way TPN DB Supply installation testing and commissioning of 8 way double door distribution board with 63A 30mA FP RCCB as incomer, 25A DP MCB-3 Nos and 12 nos 6-16A SPMCB as outgoing. (CAFÉ & JUICE BAR)	NO	1.000	15,746.04	15,746.00
14	1308293 SAC 9965 8 way TPN DB - Switchgears Supply installation testing and commissioning of 8 way double door distribution board with 40A 30mA FP RCCB as incomer, 25A DP MCB-3 Nos and 12 nos 6-16A SPMCB as outgoing. [(LPDB FOR DOCTORS CLINIC / FIRE CONTROL CENTER)]	NO	2.000	18,549.10	37,098.00
15	1306381 SAC 9954 6 way TPN DB Supply installation testing and commissioning of 6 way double door distribution board with 40A FPMCB + 25A 30mA RCCB as incomer and 18 nos 6-16A SPMCB. (For OWC)	NO	2.000	22,630.68	45,261.00
16	1306384 SAC 9954 8 way SPN DB	NO	3.000	8,260.05	24,780.00

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
	Supply, Installation testing and commissioning of 8 way SPN DB with 25A DP RCBO, 30mA as incomer 8 nos 6-10A SPMCB as outgoing. (LDB- S/S / ATM CENTER / ELDB-FIC)				
17	1306865 SAC 9954 6-Way SPN DB Supply installation testing and commissioning of 6way double door distribution board with 40A DP RCBO as incomer and 2nos 6-20A SPMCB, 0-24 hrs 25A Digital modular timer - (FOR GRD FL-LANDSCAPE-ELDB).	NO	1.000	9,546.96	9,547.00
18	1306865 SAC 9954 6-Way SPN DB Supply installation testing and commissioning of 6way double door distribution board with 40A DP RCBO as incomer and 2nos 6-20A SPMCB, 0-24 hrs 25A Digital modular timer - (FOR AMENITY FL-LANDSCAPE / ELV -ELDB).	NO	2.000	9,546.96	19,094.00
19	1308391 SAC 9954 8 way SPN DB-switchgear Supply, Installation testing and commissioning of 8 way SPN DB with 40A DP RCBO, 30mA as incomer 6 nos. 6-16A SP MCB as outgoing. (ELDB-B1, ELDB-B2, ELDB-GR & P1).	NO	3.000	9,109.71	27,329.00
20	1306385 SAC 9954 12 way SPN DB Supply, Installation testing and commissioning of 12 way SPN DB with 20A DP RCBO, 30mA as incomer 8 nos. 6-16A SP MCB as outgoing. [ELDB-(P2 & AMENITY- PARKING AREAS)].	NO	1.000	9,109.71	9,110.00
21	1307439 SAC 9954 Caution stickers 100 x 100 mm Supply, installation of Caution stickers 100 x 100 mm	NO	29.000	150.00	4,350.00
				Subtotal	673,626.00
				SGST 9 %	60,626.34
				CGST 9 %	60,626.34

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
4	CABLES Supply, Laying, testing and commissioning of cables on cable trays, structural supports and cable supports provided, include unloading, shifting upto site. The scope includes clamping of cables by ready made G.I. spacers, saddles or clamps fabricated out of M.S. strip 3 mm thick, Treasing and Clamping of Cable on cable tray, supply of all clamping materials and hardware etc., providing cable tags made out of aluminium strip and 75x20 mm in size with cable number and size punched on it. Cable tags shall be tied to cables at every 20 meter interval and at both the ends. Supports provided for clamping of cables upto individual motors and push-buttons shall be paid extra as per item rate for MS fabrication work. Empty cable drums shall be returned to stores. In case of laying unlisted cables, rate of cable whose outer dia is closest to the cable sizes quoted shall be applicable. The same shall hold good for cable termination also. Cables FRLS -(AL/CU/XLPE/FRLS)				
1	1300013 SAC 9954 SI of 3.5C 300sq.mm Aluminum stranded conductor Armoured Cables fixed with GI saddles & spacers or mounted on Z-Section Channels or Cable Trays which are measured separately: 3.5C X 300 SQ.MM FRLS ALUMINIUM/XLPE/SWA	MTR	462.000	2,750.00	1,270,500.00
2	1300014 SAC 9954 SI of 3.5C 240sq.mm Aluminum stranded conductor Armoured Cables fixed with GI saddles & spacers or mounted on Z-Section Channels or Cable Trays which are measured separately: 3.5C X 240 SQ.MM FRLS ALUMINIUM/XLPE/SWA	MTR	140.000	2,080.00	291,200.00
3	1300015 SAC 9954 SI of 3.5C 185sq.mm Aluminum stranded conductor Armoured Cables fixed with GI saddles & spacers or mounted on Z-Section Channels or Cable Trays which are measured separately: 3.5C X 185 SQ.MM FRLS ALUMINIUM/XLPE/SWA	MTR	454.000	1,550.00	703,700.00
4	1300016 SAC 9954 SI of 3.5C 150sq.mm Aluminum stranded conductor Armoured Cables fixed with	MTR	708.000	1,460.00	1,033,680.00

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
	GI saddles & spacers or mounted on Z-Section Channels or Cable Trays which are measured separately: 3.5C X 150 SQ.MM FRLS ALUMINIUM/XLPE/SWA				
5	1300017 SAC 9954 SI of 3.5C 120sq.mm Aluminum stranded conductor Armoured Cables fixed with GI saddles & spacers or mounted on Z-Section Channels or Cable Trays which are measured separately: 3.5C X 120 SQ.MM FRLS ALUMINIUM/XLPE/SWA	MTR	798.000	1,245.00	993,510.00
6	1300018 SAC 9954 SI of 3.5C 95sq.mm Aluminum stranded conductor Armoured Cables fixed with GI saddles & spacers or mounted on Z-Section Channels or Cable Trays which are measured separately: 3.5C X 95 SQ.MM FRLS ALUMINIUM/XLPE/SWA	MTR	120.000	800.00	96,000.00
7	1300020 SAC 9954 SI of 3.5C 50sq.mm Aluminum stranded conductor Armoured Cables fixed with GI saddles & spacers or mounted on Z-Section Channels or Cable Trays which are measured separately: 3.5C X 50 SQ.MM FRLS ALUMINIUM/XLPE/SWA	MTR	110.000	635.29	69,882.00
8	1300021 SAC 9954 SI of 3.5C 35sq.mm Aluminum stranded conductor Armoured Cables fixed with GI saddles & spacers or mounted on Z-Section Channels or Cable Trays which are measured separately: 3.5C X 35 SQ.MM FRLS ALUMINIUM/XLPE/SWA	MTR	373.000	473.86	176,750.00
9	1306818 SAC 9954 4C 25sq.mm Aluminum 4C X 25 SQ.MM FRLS ALUMINIUM/XLPE/SWA	RMT	60.000	427.00	25,620.00
10	1300023 SAC 9954 SI of 4C 16sq.mm Aluminum stranded conductor Armoured Cables fixed with GI saddles & spacers or mounted on Z-Section Channels or Cable Trays which are measured separately: 4C X 16 SQ.MM FRLS ALUMINIUM/XLPE/SWA	MTR	965.000	300.00	289,500.00

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
11	1300024 SAC 9954 SI 4C 10sqmm Alumstranded cond Armrd 4C X 10 SQ.MM FRLS ALUMINIUM/XLPE/SWA	MTR	167.000	225.00	37,575.00
12	1300682 SAC 9954 S 4C # 10 SQ. MM CU XLPE ARM. FRLS 4C X 10 SQ.MM FRLS COPPER/XLPE/SWA	RMT	121.000	824.15	99,722.00
13	1300683 SAC 9954 S 4C # 6 SQ. MM CU XLPE ARM. FRLS 4C X 6 SQ.MM FRLS COPPER/XLPE/SWA	RMT	30.000	527.00	15,810.00
14	1303795 SAC 9954 Supply of 4C x 4sqmm Copper Cable. 4C X 4 SQ.MM FRLS COPPER/XLPE/SWA	RMT	805.000	300.00	241,500.00
15	1307739 SAC 9954 3C 10 sq.mm FRLS Copper 3C X 10 SQ.MM FRLS COPPER/XLPE/SWA	RMT	267.000	550.00	146,850.00
16	1300030 SAC 9954 SI of 3C 6sq.mm copper stranded conductor Armoured Cables fixed with GI saddles & spacers or mounted on Z-Section Channels or Cable Trays which are measured separately: 3C X 6 SQ.MM FRLS COPPER/XLPE/SWA	MTR	209.000	354.00	73,986.00
17	1300031 SAC 9954 SI of 3C 4sq.mm copper stranded conductor Armoured Cables fixed with GI saddles & spacers or mounted on Z-Section Channels or Cable Trays which are measured separately: 3C X 4 SQ.MM FRLS COPPER/XLPE/SWA	MTR	1,000.000	250.00	250,000.00
18	1308312 SAC 9965 3C X 2.5 sq.mm FRLS Cu Cable 3C X 2.5 SQ.MM FRLS COPPER/XLPE/SWA	MTR	2,500.000	185.00	462,500.00
19	1308841 SAC 9954 SITC 3C 1.5 sq.mm.XLPE Cu flexible cable 3C X 1.5 SQ.MM FRLS COPPER/XLPE/SWA	RMT	1,500.000	158.00	237,000.00
20	1309123 SAC 9954	RMT	162.400	339.00	55,054.00

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
	4C X 240 SQ.MM FS COPPER/SWA 4C X 240 SQ.MM FS COPPER/SWA				
21	1306178 SAC 9954 3.5 C x 185 sq. mm FS copper cable "Service to be read as : - 4C X 185 SQ.MM FS COPPER/SWA"	MTR	580.000	260.00	150,800.00
22	1306180 SAC 9954 3.5 C x 120 sq. mm FS copper cable Service shall be read as :- 4C X 120 SQ.MM FS COPPER/SWA	MTR	15.000	263.00	3,945.00
23	1303595 SAC 9954 Laying of 4C, 95sqmm armoured cable 4C X 95 SQ.MM FS COPPER/SWA	RMT	145.000	128.00	18,560.00
24	1306183 SAC 9954 3.5 C x 50 sq. mm FS copper cable Service to be read as : - 4C X 50 SQ.MM FS COPPER/SWA	MTR	339.250	97.00	32,907.00
25	1306184 SAC 9954 4 C x 35 sq. mm FS copper cable 4C X 35 SQ.MM FS COPPER/SWA	MTR	367.250	92.00	33,787.00
26	1308331 SAC 9965 4C X 25 sq.mm FS copper Cable 4CX25 SQ.MM FSCOPPER /SWA	MTR	30.000	65.00	1,950.00
27	1306187 SAC 9954 4C x 10 sq. mm FS copper cable 4C X 10 SQ.MM FS COPPER/SWA	MTR	55.000	55.00	3,025.00
28	1306188 SAC 9954 4C x 6 sq. mm FS copper cable 4C X 6 SQ.MM FS COPPER/SWA	MTR	381.450	52.00	19,835.00
29	1309124 SAC 9954 3C X 50 SQ.MM FS COPPER/SWA 3C X 50 SQ.MM FS COPPER/SWA	RMT	240.000	97.00	23,280.00
30	1306191 SAC 9954 3C x 10 sq. mm FS copper cable 3C X 10 SQ.MM FS COPPER/SWA	MTR	80.000	52.00	4,160.00
31	1306192 SAC 9954 3C x 6 sq. mm FS copper cable 3C X 6 SQ.MM FS COPPER/SWA	MTR	475.000	52.00	24,700.00
				Subtotal	6,887,288.00
				SGST 9 %	619,855.92
				CGST 9 %	619,855.92

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
5	CABLE TERMINATION Providing & Installation of cable terminations for the XLPE cables including Double/Single compression type chrome plated brass glands and lugs (crimping type), PVC taping as required and all accessories complete. including & upto 150 sqmm cable single compression glands and above 150 sqmm double compression glands shall be considered.				
1	1300043 SAC 9954 Providing End Terminations for the 3.5C 300sq.mm Aluminum Armoured Cables. 3.5C X 300 SQ.MM FRLS ALUMINIUM/XLPE/SWA	NO	16.000	1,850.00	29,600.00
2	1300044 SAC 9954 Providing End Terminations for the 3.5C 240sq.mm Aluminum Armoured Cables with brass cable glands & copper lugs: 3.5C X 240 SQ.MM FRLS ALUMINIUM/XLPE/SWA	NO	8.000	1,850.00	14,800.00
3	1300045 SAC 9954 Providing End Terminations for the 3.5C 185sq.mm Aluminum Armoured Cables with brass cable glands & copper lugs: 3.5C X 185 SQ.MM FRLS ALUMINIUM/XLPE/SWA	NO	6.000	1,750.00	10,500.00
4	1300046 SAC 9954 Providing End Terminations for the 3.5C 150sq.mm Aluminum Armoured Cables with brass cable glands & copper lugs: 3.5C X 150 SQ.MM FRLS ALUMINIUM/XLPE/SWA	NO	10.000	1,700.00	17,000.00
5	1300047 SAC 9954 Providing End Terminations for the 3.5C 120sq.mm Aluminum Armoured Cables with brass cable glands & copper lugs: 3.5C X 120 SQ.MM FRLS ALUMINIUM/XLPE/SWA	NO	18.000	1,700.00	30,600.00
6	1300048 SAC 9954 Providing End Terminations for the 3.5C 95sq.mm Aluminum Armoured Cables with brass cable glands & copper lugs: 3.5C X 95 SQ.MM FRLS ALUMINIUM/XLPE/SWA	NO	2.000	1,650.00	3,300.00
7	1300050 SAC 9954 Providing End Terminations for the 3.5C 50sq.mm Aluminum Armoured Cables with brass cable glands & copper lugs:	NO	2.000	650.00	1,300.00

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
	3.5C X 50 SQ.MM FRLS ALUMINIUM/XLPE/SWA				
8	1300051 SAC 9954 Providing End Terminations for the 3.5C 35sq.mm Aluminum Armoured Cables with brass cable glands & copper lugs: 3.5C X 35 SQ.MM FRLS ALUMINIUM/XLPE/SWA	NO	8.000	650.00	5,200.00
9	1302322 SAC 9954 End termination of 4 core 25 sqmm al. armoured cables 4C X 25 SQ.MM FRLS ALUMINIUM/XLPE/SWA	NO	6.000	650.00	3,900.00
10	1302323 SAC 9954 End termination of 4 core 16 sqmm al. armoured cables 4C X 16 SQ.MM FRLS ALUMINIUM/XLPE/SWA	NO	24.000	650.00	15,600.00
11	1300054 SAC 9954 Providing End Terminations for the 4C 10sq.mm Aluminum Armoured Cables. 4C X 10 SQ.MM FRLS ALUMINIUM/XLPE/SWA	NO	6.000	650.00	3,900.00
12	1300055 SAC 9954 Providing End Terminations for the 4C 10sq.mm copper Armoured Cables with brass cable glands & copper lugs: 4C X 10 SQ.MM FRLS COPPER/XLPE/SWA	NO	2.000	650.00	1,300.00
13	1300056 SAC 9954 Providing End Terminations for the 4C 6sq.mm copper Armoured Cables. 4C X 6 SQ.MM FRLS COPPER/XLPE/SWA	NO	4.000	650.00	2,600.00
14	1300057 SAC 9954 Providing End Terminations for the 4C 4sq.mm copper Armoured Cables with brass cable glands & copper lugs: 4C X 4 SQ.MM FRLS COPPER/XLPE/SWA	NO	36.000	650.00	23,400.00
15	1308598 SAC 9954 P&F End term of 3C X 10 sq.mm Cu Wire 3C X 10 SQ.MM FRLS COPPER/XLPE/SWA	NO	8.000	650.00	5,200.00
16	1300060 SAC 9954 Providing End Terminations for the 3C	NO	4.000	650.00	2,600.00

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
	6sq.mm copper Armoured Cables with brass cable glands & copper lugs: 3C X 6 SQ.MM FRLS COPPER/XLPE/SWA				
17	1300062 SAC 9954 Providing End Terminations for the 3C 2.5sq.mm copper Armoured Cables with brass cable glands & copper lugs: 3C X 2.5 SQ.MM FRLS COPPER/XLPE/SWA	NO	500.000	400.00	200,000.00
18	1303927 SAC 9954 End term of 3C 1.5 sqmm cu. armour Cab 3C X 1.5 SQ.MM FRLS COPPER/XLPE/SWA	NO	200.000	400.00	80,000.00
19	1309126 SAC 9954 4C X 240 SQ.MM FS COPPER/SWA 4C X 240 SQ.MM FS COPPER/SWA	NO	16.000	1,850.00	29,600.00
20	1309127 SAC 9954 4C X 185 SQ.MM FS COPPER/SWA 4C X 185 SQ.MM FS COPPER/SWA	NO	8.000	1,850.00	14,800.00
21	1306231 SAC 9954 End term 3.5Cx120 sq. mm FS Copper Service to be read as : - 4C X 120 SQ.MM FS COPPER/SWA.	NO	2.000	1,750.00	3,500.00
22	1301062 SAC 9954 Providing End Term 4C 95sqmm Cable 4C X 95 SQ.MM FS COPPER/SWA	NO	4.000	1,550.00	6,200.00
23	1302640 SAC 9954 Providing End Terminations for the 4C 50sq.mm Aluminum Armoured Cables. Service to be read as : - 4C X 50 SQ.MM FS COPPER/SWA.	NO	4.000	1,850.00	7,400.00
24	1306235 SAC 9954 End term 4Cx35 sq. mm FS Copper 4C X 35 SQ.MM FS COPPER/SWA	NO	8.000	1,850.00	14,800.00
25	1308086 SAC 9954 Cable term 4C x 25 sq. mm FS Copper 4CX 25 SQ.MM FSCOPPER /SWA	NO	4.000	1,850.00	7,400.00
26	1306238 SAC 9954 End term 4C x 10 sq. mm FS Copper 4C X 10 SQ.MM FS COPPER/SWA	NO	2.000	1,850.00	3,700.00
27	1306239 SAC 9954 End term 4C x 6 sq. mm FS Copper 4C X 6 SQ.MM FS COPPER/SWA	NO	10.000	1,850.00	18,500.00



Alder Residency Private Limited

101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
28	1306241 SAC 9954 End term 3C x 10 sq. mm FS Copper 3C X 10 SQ.MM FS COPPER/SWA	NO	8.000	1,850.00	14,800.00
29	1306242 SAC 9954 End term 3C x 6 sq. mm FS Copper 3C X 6 SQ.MM FS COPPER/SWA	NO	22.000	1,850.00	40,700.00
Subtotal					612,200.00
SGST 9 %					55,098.00
CGST 9 %					55,098.00

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
6	POINT WIRING Point wiring shall be done with supply, installation, testing and commissioning of 1.5 sq mm x 3 nos wires from modular switches to light outlet in concealed manner including FRLS grade wires with ISI PVC conduit of 20/25 mm diameter 1.6-1.8 mm (MMS Grade) thickness. SITC of switches, sockets, regulators, blank plates, front plates, switchboard, PVC conduit and accessories like bends, couplers,PVC fan boxes with Hook, connectors, ferruling, junction boxes, zarri making and semi finishing etc are part of the point rate. All wire ends shall be lugged properly and ferruled at both D.B. end. All boxes shall be 1.4 mm thick GI boxes for S.B.. All wire sizes unless specified below shall be as per specifications. - limited to min. size of 1.5 sqmm.				
1	1306395 SAC 9954 Staircase MCB controlled Primary pt Primary Light point controlled by MCB/Isolator directly with 2Rx2.5 sq mm+ 1RX1.5 sqmm ckt. Cost of Isolator is not part of this item. (15 mtr considered as primary length, rest qty considered in item below.	P	6.000	2,015.82	12,095.00
2	1303040 SAC 9954 Secondary light points (from primary point to subsequent points) controlled by primary point switch. Point length considered is 4 mtrs. Secondary Light Point ('-do- as 6.1.1) looped from above with 1.5 sq mm ckt	P	24.000	1,614.92	38,758.00
3	1305563 SAC 9954 SI of 2x1.5Sqmm + 1x1.5 Sqmm Wiring With 2 x 1.5sqmm + 1 x 1.5sqmm (earth) wires in dia 20/25mm MMS PVC conduit	RMT	500.000	121.22	60,610.00
4	1306452 SAC 9954 Car Park MCB controlled Primary point Primary (first) light point controlled by a MCB (MCB cost not to be included here). (15 mtr ckt length). Location : PARKING & SERVICE & AREAS	P	50.000	2,015.82	100,791.00
5	1303040 SAC 9954 Secondary light points (from primary	P	500.000	1,280.00	640,000.00

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
	point to subsequent points) controlled by primary point switch. Point length considered is 4 mtrs. Secondary Light Point ('-do- as 6.1.2) looped from above with 1.5 sq mm ckt				
6	1306452 SAC 9954 Car Park MCB controlled Primary point Primary (first) light ping controlled by a switch. (15 mtr ckt length).	P	14.000	2,015.82	28,221.00
7	1303040 SAC 9954 Secondary light points (from primary point to subsequent points) controlled by primary point switch. Point length considered is 4 mtrs. Secondary Light Point ('-do- as 6.2.3) looped from above with 1.5 sq mm ckt.	P	40.000	1,614.92	64,597.00
8	1306673 SAC 9954 Exhaust Fan Pt -Comm area Exhaust fan point to be done with 1.5 sq mm looped wiring controlled by one 6 A switch on lighting switch board in toilet and connector at Fan end.	P	10.000	589.00	5,890.00
9	1307509 SAC 9954 6 A x 230 Volt 5 pin socket outlet point One 6 A x 5 pin 230 Volt socket outlet point controlled by one 6 A switch located on switch board.	NO	12.000	702.00	8,424.00
10	1307282 SAC 9954 6A x 230V - 5pin Socket Primary power point with 6A x 230 Volt 5 pin socket outlet point controlled by 6 A switch at convenient location including box plate etc complete to be done with 1.5 sq mm ckt from D.B. Ckt length limited upto 8mtr.	NO	5.000	667.00	3,335.00
11	1307282 SAC 9954 6A x 230V - 5pin Socket Secondary power point with 6 A x 230 Volt 5 pin socket outlet only including box plate etc complete to be done with 1.5 sq mm ckt looped from above complete with accessories.	NO	5.000	667.00	3,335.00
12	1307334 SAC 9954 6/16A x 230 Volt 5 pin socket-IP67 box 1 nos 6/16A x 230 Volt 5 pin socket outlet point with 16 A switch with box and plate complete to be done with 2.5 sq mm wire ckt from D.B. complete.	NO	10.000	2,015.82	20,158.00

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
	Ckt length limited upto 15 mtr.				
13	1307334 SAC 9954 6/16A x 230 Volt 5 pin socket-IP67 box 1 nos 6/16A x 230 Volt 5 pin socket outlet point with 16 A switch with box and plate complete (-do- as above) but looped socket with 2.5 sq mm ckt from item 6.1.13.	NO	10.000	2,015.82	20,158.00
14	1306648 SAC 9954 25mm dia flexible conduit Providing and laying of MMS PVC conduit with all conduit accessories PVC junction/pull boxes, G.I fish wire, fixing accessories etc as required for telephone and data networking complete. The rates shall include chasing of walls, floors etc & plastering the chased portion as required. 25 mm dia. ISI marked PVC corrugated flexible conduit	RMT	100.000	42.00	4,200.00
15	1301651 SAC 9954 Providing and Fixing of the 20mm dia. medium PVC conduits concealed in slab/wall or surface mounted on GI Z-section, or PVC saddles and spacers in Electrical shaft and from Electrical shaft to LV Junction box.(for Fire Alarm System, for Telephone, Cable TV and Internet Distributions upto L.V. Junction Boxes and VDP). Providing and laying of 20mm dia MMS PVC conduit with all conduit accessories PVC junction/pull boxes, G.I fish wire, fixing accessories etc as required for telephone and data networking complete. The rates shall include chasing of walls, floors etc & plastering the chased portion as required.	RMT	100.000	54.00	5,400.00
16	1301650 SAC 9954 Providing and Fixing of the 25mm dia. medium PVC conduits concealed in slab/wall or surface mounted on GI Z-section, or PVC saddles and spacers in Electrical shaft and from Electrical shaft to LV Junction box.(for Fire Alarm System, for Telephone, Cable TV and Internet Distributions upto L.V. Junction Boxes and VDP). Providing and laying of 25mm dia MMS PVC conduit with all conduit accessories PVC junction/pull boxes, G.I fish wire, fixing accessories etc as required for telephone and data networking complete.	RMT	250.000	69.00	17,250.00

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
	The rates shall include chasing of walls, floors etc & plastering the chased portion as required.				
17	1301649 SAC 9954 Providing and Fixing of the 32mm dia. medium PVC conduits concealed in slab/wall or surface mounted on GI Z-section, or PVC saddles and spacers in Electrical shaft and from Electrical shaft to LV Junction box.(for Fire Alarm System, for Telephone, Cable TV and Internet Distributions upto L.V. Junction Boxes and VDP). Providing and laying of 32mm dia MMS PVC conduit with all conduit accessories PVC junction/pull boxes, G.I fish wire, fixing accessories etc as required for telephone and data networking complete. The rates shall include chasing of walls, floors etc & plastering the chased portion as required.	RMT	250.000	105.00	26,250.00
18	1305499 SAC 9954 2 x 2.5 + 1 x 1.5 sq.mm copper wire. MAINS : - For three/single phase DB to Light/ industrial sockets / D.B. to D.B./D.B. to Isolator / panel to UPS and UPS to UPS DB including TERMINATION AT BOTH END. 2 x 2.5 sq mm + 1 x 1.5 sq mm FRLS copper flexible wires in and including 20 mm dia rigid PVC conduit of FR grade with wall thickness of 1.6-1.8 mm (MMS Grade). (For lighting)	RMT	1,000.000	99.00	99,000.00
19	1308269 SAC 9965 2 x 1.5 sq mm + 1 x 1.5 sq mm cu wire MAINS : - For three/single phase DB to Light/ industrial sockets / D.B. to D.B./D.B. to Isolator / panel to UPS and UPS to UPS DB including TERMINATION AT BOTH END. 2 x 1.5 sq mm + 1 x 1.5 sq mm FRLS copper flexible wires in and including 20 mm dia rigid PVC conduit of FR grade with wall thickness of 1.6-1.8 mm (MMS Grade). (For lighting)	RMT	1,000.000	76.00	76,000.00
20	1305500 SAC 9954 2 x 4 + 1 x 2.5 sq.mm copper wire. MAINS : - For three/single phase DB to Light/ industrial sockets / D.B. to D.B./D.B. to Isolator / panel to UPS and UPS to UPS DB including TERMINATION AT BOTH END.	RMT	150.000	153.00	22,950.00

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
	2 x 4 sq mm + 1 x 2.5 sq mm FRLS copper flexible wires in and including 25 mm dia rigid PVC conduit of FR grade with wall thickness of 1.8-2.0 mm (MMS Grade).				
21	1305568 SAC 9954 SI of 4x2.5 Sqmm + 1x1.5 Sqmm MAINS : - For three/single phase DB to Light/ industrial sockets / D.B. to D.B./D.B. to Isolator / panel to UPS and UPS to UPS DB including TERMINATION AT BOTH END. Service to be read as : - 4 x 2.5 sq mm + 2 x 1.5 sq mm FRLS copper flexible wires in and including 25 mm dia rigid PVC conduit of FR grade with wall thickness of 1.8-2.0 mm (MMS Grade).	RMT	40.000	259.27	10,371.00
22	1307150 SAC 9954 S/F 4 x 4 + 1 x 2.5 sq.mm copper wire. MAINS : - For three/single phase DB to Light/ industrial sockets / D.B. to D.B./D.B. to Isolator / panel to UPS and UPS to UPS DB including TERMINATION AT BOTH END. 4 x 4 sq mm + 1 x 2.5 sq mm FRLS copper flexible wires in and including 32 mm dia rigid PVC conduit of FR grade with wall thickness of 1.8-2.0 mm (MMS Grade).	RMT	100.000	332.00	33,200.00
				Subtotal	1,300,993.00
				SGST 9 %	117,089.37
				CGST 9 %	117,089.37

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
7	LIGHT FIXTURES & FANS : Installation, testing & commissioning of standard light fittings and lighting accessories including lamp. The scope shall include, providing of all hardware such as nuts,anchor fasteners, bolts, screws, cleats, clamps, PVC insulated wires / cables from Junction box to lighting fixtures, ball and socket arrangement with J.B., suspension conduit pipe for drop for fluorescent fitting. The cost of fabrication and installation of MS supports will be paid extra as per rates quoted elsewhere. All fixtures shall be with Electronic ballasts of APFC type. COMMON AREA & Amenity LIGHT FITTINGS				
1	1307518 SAC 9954 Fix of Surface mounted 28 W FTL fixture 28W LED SURFACE/ WALL/ SUSPENDED TYPE LIGHT FIXTURES WITH IP65 PROTECTION, EXTRUDED AL. HOUSING. Location : COMMON AREA & Amenity LIGHT FITTINGS.	NO	600.000	200.00	120,000.00
2	1300492 SAC 9954 Installation of Surface mounted fixture 28W LED,RECESSED / SURFACE MOUNTED CIRCULAR LIGHT FIXTURES Location : COMMON AREA & Amenity LIGHT FITTINGS	NO	50.000	200.00	10,000.00
3	1301812 SAC 9954 Fixing of Ceiling Fan. CEILING FAN Location : CEILING FAN	NO	15.000	200.00	3,000.00
4	1302825 SAC 9954 Installation, testing and commissioning of Recessed Wall/Step Light. STEP LIGHT Location : AMENITY & GROUND LANDSCAPE LIGHT FITTINGS	NO	73.000	200.00	14,600.00
5	1307522 SAC 9954 Fixing of Flood light fixtures FLOOD LIGHT Location : AMENITY & GROUND LANDSCAPE LIGHT FITTINGS	NO	10.000	200.00	2,000.00
6	1308842 SAC 9954	NO	43.000	200.00	8,600.00

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
	Fixing,T&C 50W Exterior post top LED POST TOP LIGHT Location : AMENITY & GROUND LANDSCAPE LIGHT FITTINGS				
7	1303091 SAC 9954 Fixing of External wall light. WALL LIGHT (ON WALL) Location : AMENITY & GROUND LANDSCAPE LIGHT FITTINGS	NO	38.000	200.00	7,600.00
8	1305137 SAC 9954 Under Water light for Pool UNDERWATER LIGHT Location : AMENITY & GROUND LANDSCAPE LIGHT FITTINGS	NO	13.000	200.00	2,600.00
9	1305768 SAC 9954 Recessed LED Light RECESSED DOWN LIGHT Location : AMENITY & GROUND LANDSCAPE LIGHT FITTINGS	RMT	3.000	200.00	600.00
10	1308604 SAC 9954 Fixing of Pole Light Location : AMENITY & GROUND LANDSCAPE LIGHT FITTINGS	NO	24.000	200.00	4,800.00
11	1303091 SAC 9954 Fixing of External wall light. WALL LIGHT (ON COLUMNS) Location : AMENITY & GROUND LANDSCAPE LIGHT FITTINGS	NO	56.000	200.00	11,200.00
12	1301812 SAC 9954 Fixing of Ceiling Fan. Location : AMENITY & GROUND LANDSCAPE LIGHT FITTINGS	NO	3.000	200.00	600.00
13	1303774 SAC 9954 ITC of Luminaire on Pole. IN GROUND LUMINAIRE-WALL WASHER Location : AMENITY & GROUND LANDSCAPE LIGHT FITTINGS	NO	55.000	200.00	11,000.00
Subtotal					196,600.00
SGST 9 %					17,694.00
CGST 9 %					17,694.00

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
8	EARTHING				
1	1303233 SAC 9954 Making of Copper Earthing Pit. Providing and laying of 600 x 600 x 3.15 mm thick tined copper plate electrode, with 2 Nos 50 x 6 mm copper strips from earth plate electrode to inspection chamber, 50 mm dia medium class GI pipe, CI funnel with 20 gauge GI wire mesh, masonry chamber 1000 x 500 mm with concrete base C I heavy duty / chequered plate manhole cover with frame painted with bitumastic paint and packing with mixture of charcoal and common salt around plate electrode including digging of pit upto permanent moisture level and as per soil condition but not less than 3 meters and back filling as required complete with chamber, Heavy Duty lid cover and tap off & test point as IS 3043 -1987. Supply & making of Earthing station with the use of 19/32mm dia. copper bonded rod, 3 mtr long and filling of 50 kg of compound complete with chamber, lid cover and tap off & test point.	NO	28.000	18,500.00	518,000.00
2	1303008 SAC 9954 Carrying Out Misc. Electrical Work Service to be read as : - Supply of Ground Resistance Lowering Compound 20Kg Bag for normal soil condition. It should be free from carbon & graphite and conductive in nature. It should accommodate 60% of water of its volume.	NO	20.000	680.00	13,600.00
3	1308300 SAC 9965 50X6 mm CU strip Supply and Laying Cu./GI. earthing strips for interconnecting the earthing stations, panels, DB's etc. in built-up trenches, on walls/ceiling, buried in ground generally as specified and shown on drawings complete with : Size : 50 x 6 mm Cu. Strip	RMT	50.000	2,649.00	132,450.00
4	1308045 SAC 9954 32x6 mm CU strip Supply and Laying Cu./GI. earthing strips for interconnecting the earthing stations, panels, DB's etc. in built-up trenches, on walls/ceiling, buried in ground generally as specified and shown on drawings complete with :	RMT	200.000	2,362.00	472,400.00

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
	Size : 32 x 6 mm Cu. Strip				
5	1305728 SAC 9954 19 x 3 mm cu. Strip Supply and Laying Cu./Gl. earthing strips for interconnecting the earthing stations, panels, DB's etc. in built-up trenches, on walls/ceiling, buried in ground generally as specified and shown on drawings complete with : Size : 19 x 3 mm Cu. Strip.	RMT	40.000	1,437.00	57,480.00
6	1307311 SAC 9954 50 x 6 mm Gl. Strip Supply and Laying Cu./Gl. earthing strips for interconnecting the earthing stations, panels, DB's etc. in built-up trenches, on walls/ceiling, buried in ground generally as specified and shown on drawings complete with : Size : 50 x 6 mm Gl. Strip	RMT	850.000	382.00	324,700.00
7	1303524 SAC 9954 Supply, installation, testing & commissioning 32 x 6mm Gl strip. Supply and Laying Cu./Gl. earthing strips for interconnecting the earthing stations, panels, DB's etc. in built-up trenches, on walls/ceiling, buried in ground generally as specified and shown on drawings complete with : Size : 32 x 6 mm Gl. Strip	RMT	600.000	275.00	165,000.00
8	1307312 SAC 9954 25 x 6 mm Gl. Strip Supply and Laying Cu./Gl. earthing strips for interconnecting the earthing stations, panels, DB's etc. in built-up trenches, on walls/ceiling, buried in ground generally as specified and shown on drawings complete with : Size : 25 x 6 mm Gl. Strip	RMT	600.000	250.00	150,000.00
9	1306693 SAC 9954 8 Gauge bare Gl earth wire. SITC of 8 gauge bare Gl. wire	RMT	800.000	45.00	36,000.00
10	1305734 SAC 9954 8G bare Cu. Wire SITC of 8 gauge bare CU. Wire	RMT	200.000	215.00	43,000.00
11	1309129 SAC 9954 4.0 sqmm FRLS Copper Flexible PVC wire 4 sqmm FRLS Copper Flexible PVC wire	RMT	100.000	65.00	6,500.00



Alder Residency Private Limited

101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
12	1308375 SAC 9965 Equipotential bars-600x50x6mm GI Equipotential bars 600mmX50mmX6mm GI.	NO	4.000	1,800.00	7,200.00
13	1308630 SAC 9965 Equipotential bar # 300x25x6 GI Equipotential bars 300mmX25mmX6mm GI.	NO	4.000	800.00	3,200.00
14	1308616 SAC 9954 Equipotential bars-200x25x6mm GI Service to be read as : - Equipotential bars - 200mm X 19mm X 3mm CU.	NO	1.000	650.00	650.00
				Subtotal	1,930,180.00
				SGST 9 %	173,716.20
				CGST 9 %	173,716.20

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
9	MISCELLANEOUS WORKS				
1	1306465 SAC 9954 S/F of 50mm PVC Conduit SITC of 50mm dia PVC pipe of heavy gauge with bends / couplers etc complete with accessories to mount the same within shaft / suspend with help of threaded rod / slotted angle from ceiling etc complete.	RMT	100.000	180.00	18,000.00
2	1300185 SAC 9954 PVC Pipe for Cable 100mm dia. SITC of 100mm dia PVC pipe of heavy gauge with bends / couplers etc complete with accessories to mount the same within shaft / suspend with help of threaded rod / slotted angle from ceiling etc complete.	MTR	100.000	225.00	22,500.00
3	1303675 SAC 9954 Supply & Fixing of 25mm GI Conduit. SITC of ISI marked B-Class 25mm dia GI conduit with all necessary accessories, bends , couplers etc complete.	RMT	250.000	310.00	77,500.00
4	1307597 SAC 9954 Supply of 32mm dia. Conduits SITC of ISI marked B-Class 32mm dia GI conduit with all necessary accessories, bends , couplers etc complete.	RMT	100.000	360.00	36,000.00
5	1308995 SAC 9954 SI MS Steel Supply and erecting fabricated support works / stands etc complete fabricated as per details given from MS flat / angle / plates etc complete with 2 coats of red oxide and 2 coats of paint on the same along with mounting of supports with use of necessary hardwares complete.	KG	500.000	180.00	90,000.00
6	1307319 SAC 9954 3way Junction box - 10A Busbars SITC of IP 65 category PVC type junction boxes with necessary loop in loop out connectors / busbars / internal wiring if required etc. complete. The boxes if required shall be mounted on 9" MS supports which shall be considered in cost. 3way Junction box	NO	10.000	396.00	3,960.00
7	1307320 SAC 9954 3 way Junction box - 16A Busbars SITC of IP 65 category PVC type junction	NO	10.000	396.00	3,960.00

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
	boxes with necessary loop in loop out connectors / busbars / internal wiring if required etc. complete. The boxes if required shall be mounted on 9" MS supports which shall be considered in cost. 3way Junction box				
8	1307487 SAC 9954 S 4way Junction box - 10A Busbars SITC of IP 65 category PVC type junction boxes with necessary loop in loop out connectors / busbars / internal wiring if required etc. complete. The boxes if required shall be mounted on 9" MS supports which shall be considered in cost. 4way Junction box	NO	10.000	475.00	4,750.00
9	1307321 SAC 9954 4 way Junction box - 16A Busbars SITC of IP 65 category PVC type junction boxes with necessary loop in loop out connectors / busbars / internal wiring if required etc. complete. The boxes if required shall be mounted on 9" MS supports which shall be considered in cost. 4 way Junction box.	NO	10.000	475.00	4,750.00
10	1303186 SAC 9954 ITC UPS Installation, testing and commissioning of 40 KVA UPS, three phase input and three phase output online IGBT based UPS with 0.9 output p.f. with 15minutes battery back up. - For Emergency Lighting	NO	1.000	45,000.00	45,000.00
				Subtotal	306,420.00
				SGST 9 %	27,577.80
				CGST 9 %	27,577.80

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
10	CONDUITING AND CABLING FOR TV				
1	1301651 SAC 9954 Providing and Fixing of the 20mm dia. medium PVC conduits concealed in slab/wall or surface mounted on GI Z-section, or PVC saddles and spacers in Electrical shaft and from Electrical shaft to LV Junction box.(for Fire Alarm System, for Telephone, Cable TV and Internet Distributions upto L.V. Junction Boxes and VDP). Providing and fixing in position 20mm dia conduit MMS FRLS PVC conduits concealed or exposed as called for including all accessories i.e. bends, junction boxes, outlet boxes with cover plates of approved make and design.	RMT	500.000	54.00	27,000.00
2	1301650 SAC 9954 Providing and Fixing of the 25mm dia. medium PVC conduits concealed in slab/wall or surface mounted on GI Z-section, or PVC saddles and spacers in Electrical shaft and from Electrical shaft to LV Junction box.(for Fire Alarm System, for Telephone, Cable TV and Internet Distributions upto L.V. Junction Boxes and VDP). Providing and fixing in position 25mm dia conduit MMS FRLS PVC conduits concealed or exposed as called for including all accessories i.e. bends, junction boxes, outlet boxes with cover plates of approved make and design.	RMT	500.000	69.00	34,500.00
3	1301649 SAC 9954 Providing and Fixing of the 32mm dia. medium PVC conduits concealed in slab/wall or surface mounted on GI Z-section, or PVC saddles and spacers in Electrical shaft and from Electrical shaft to LV Junction box.(for Fire Alarm System, for Telephone, Cable TV and Internet Distributions upto L.V. Junction Boxes and VDP). Providing and fixing in position 32mm dia conduit MMS FRLS PVC conduits concealed or exposed as called for including all accessories i.e. bends, junction boxes, outlet boxes with cover plates of approved make and design.	RMT	300.000	105.00	31,500.00
4	1306319 SAC 9954 10 pair armoured riser cable Supply, installation, testing and commissioning of 10 pair armoured Riser	MTR	100.000	190.00	19,000.00

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
	cable consisting of multiple core or solid copper conductors of 24 AWG size insulated with expanded polyethylene covered by a PVC skin and inner shielding for grounding. The core shall be covered by a layer of plastic tape and overlaid with a corrugated PVC plastic. The cable shall be as per the specifications laid down in the tender.				
5	1306342 SAC 9954 20 pair armoured riser cable Supply, installation, testing and commissioning of 20 pair armoured Riser cable consisting of multiple core or solid copper conductors of 24 AWG size insulated with expanded polyethylene covered by a PVC skin and inner shielding for grounding. The core shall be covered by a layer of plastic tape and overlaid with a corrugated PVC plastic. The cable shall be as per the specifications laid down in the tender.	MTR	100.000	210.00	21,000.00
6	1306345 SAC 9954 SI of 2 pair telephone cable Supply and laying for telephone/intercom system using 2-Pair 0.5SQMM in existing 20/25mm dia heavy gauge PVC conduit with all necessary accessories of wires.complete as required including the termination of wires.	MTR	1,000.000	38.00	38,000.00
7	1306353 SAC 9954 SI of 10 pair Krone type tag block Supplying, erecting & commissioning MDF with necessary hardware as required. Krone Module rate shall be excluded. 10 pair Krone type tag block	NO	1.000	319.00	319.00
8	1306354 SAC 9954 SI of 20 pair Krone type tag block Supplying, erecting & commissioning MDF with necessary hardware as required. Krone Module rate shall be excluded. 20 pair Krone type tag block	NO	1.000	558.00	558.00
9	1300944 SAC 9954 SI of 10 Pair Krone Module Telephone Tag Blocks. Supply, installation, testing and commissioning of 10-PAIR Krone Module with base frame.	NO	3.000	160.00	480.00

**Alder Residency Private Limited**101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Sr No	Description & SAC Code	Unit	Quantity	Rate (INR)	Amount (INR)
10	1306374 SAC 9954 SI Single outlet face plate RJ-11 jack Supply, installation, testing and commissioning of clip on type Voice outlets- RJ11 mounted on a GI outlet box with front plate and all necessary accessories complete. Single outlet face plate with RJ-11 jack	NO	10.000	389.00	3,890.00
11	1307222 SAC 9954 S&I CAT 6 wire in 20mm Conduit Supply and wiring Cat-6 cable in existing 20/25mm dia heavy gauge PVC conduit with all necessary accessories of wires complete as required.	NO	1,800.000	44.00	79,200.00
12	1301990 SAC 9954 Supply & installation RJ 45 socket with plate. Supply, installation, testing and commissioning of plug on type data point RJ 45 mounted on a GI outlet box with front plate and all necessary accessories complete.	NO	10.000	843.00	8,430.00
13	1306360 SAC 9954 SI of TV signal outlet Supply and fixing TV signal outlets with grid plate in GI box complete including cutting, chases, fixing of GI boxes and making good.	NO	5.000	411.00	2,055.00
14	1306364 SAC 9954 SI of two way (S2) splitter box Supply, erection, testing and commissioning of splitter with boxes : Two way (S 2)	NO	1.000	854.00	854.00
15	1306366 SAC 9954 SI of four way (S4) splitter box Supply, erection, testing and commissioning of splitter with boxes : Four way (S 4)	NO	1.000	1,157.00	1,157.00
16	1307887 SAC 9954 S/I of RG-6 Coaxial Cable - CTV Submains Supply, laying, connecting and commissioning of RG-6 co-axial cable of MATV as per specification in existing conduit.	RMT	400.000	37.50	15,000.00
Subtotal					282,943.00
SGST 9 %					25,464.87
CGST 9 %					25,464.87
Total					14,989,166



Alder Residency Private Limited

101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Total SGST **1,349,025**

Total CGST **1,349,025**

Grand Total **17,687,216**

In Words **RUPEES ONE CRORE SEVENTY SIX LAKH EIGHTY SEVEN THOUSAND TWO HUNDRED SIXTEEN ONLY**

Thanking you,

Yours truly,

For **Alder Residency Private Limited**

HEAD CONTRACT

CLUSTER HEAD

GM CONTRACT

PRESIDENT

DIRECTOR OPERATION



Alder Residency Private Limited

101, KALPATARU SYNERGY, OPP.GRAND HYATT HOTEL, SANTACRUZ EAST,,MUMBAI
400055,Maharashtra

Acknowledgement:

I / We hereby acknowledge receipt of service order copy and hereby agree to comply with all terms & conditions stipulated therein and agree that this service order shall form a part of the contract document and Agreement between us.

We Confirm & Unconditionally Accept
For **Private Company H. N. POWER SOLUTIONS PRIVATE LIMITED**

SIGNATURE

- (1) Name of the person :
(2) Designation - Proprietor/Partner :

As per the details provided by you, your Bank details as per our records are as under:

Bank Name :- ICICI BANK LIMITED

IFSC code :- ICIC0000203

Account No. :- XXXXXXXX1387

You hereby confirm and acknowledge receipt of money, as and when remitted by us into the above mentioned Bank Account at any point of time herein after without any dispute thereof.

You further undertake to:

- 1) Keep us informed in writing instantly about any changes in the aforesaid bank details as well as details of email id/s/mobile no.
- 2) Inform us on any wrong/excess/erroneous money received by you.
- 3) Refund any wrong/excess/erroneous payment of money received by you in case of erroneous transfer of funds to your account within 7 days of receipt of intimation from us in that regard.
- 4) Authorize us to adjust such wrong / excess / erroneous payment mentioned in point no 2 above against any of the outstanding payments payable by us to you.
- 5) Execute / sign such other papers as may be called upon by us in this regard.