

WORK ORDER

Vendor Address :
H N Power Solutions Private Limited
1st Floor
Shop No 111
Swastik Platinum
Dwarli
Thane 421306
Kind Attn. : Rajan Dubey
Contact No.: 9833366785

WO No. : 4100017044
WO Date : 21.08.2025
Validity: 21.08.2025 To 21.04.2027
PAN No. : AAHCH3594E
PF No. : THTHA3290463000
EM No. : UDYAM-MH-33-0124969
V-GST No. : 27AAHCH3594E1ZF

Godrej Properties Limited
5TH FLOOR, GODREJ ONE,
PIROJSHANAGAR,
EASTERN,EXPRESS HIGHWAY,
VIKROLI EAST, Mumbai City,
Mumbai 400079
022-66510200
022-22072044
www.godrejproperties.com
GST No. : 27AAACG3995M1Z1

Project : Ambivali Project

Sr. No.	Service Code / Description	Total Value
1	ELECTRICAL PANELS	3,010,364.00
2	CABLE TRAY	3,137,975.00
3	DISTRIBUTION BOARDS - FACTORY FABRICATED	52,300.00
4	CABLES	4,553,080.50
5	CABLE TERMINATION	343,387.50
6	POINT WIRING & CONDUITING	2,704,400.50
7	LIGHT FIXTURES & FANS	221,160.00
8	UPS/ INVERTER WORKS	198,125.00
9	EARTHING	511,459.30

Payment Terms :

4. Payment Terms and Conditions:

Contractor to raise RA bills on from 1st to 5th of every month. RA bills shall be paid within 30 days after submission of commercially correct tax invoice.

Note: - All Requisite documents as per GPL Standards shall be enclosed with Proforma Invoice <(>&<)> Tax Invoice.

For Point Wiring Items:

1. 20% on Completion of Slab conduiting Works on pro rata basis.

Total Basic Value	14,732,251.80
Total after Discount	14,732,251.80
SGST	1,325,902.68
CGST	1,325,902.68
Total WO Value	17,384,057.16

Total WO Value : RUPEES ONE CRORE SEVENTY THREE LAKH EIGHTY FOUR THOUSAND FIFTY SEVEN & PAISE SIXTEEN ONLY

Billing Address:

Ambivali - Common, Village Vadavali,,
Kalyan Taluka, Ambivli, 421102,
INDIA, ,
,

For Godrej Properties Limited

Authorized Signatory

Acknowledgement :

Vendor Address :

H N Power Solutions Private Limited
1st Floor
Shop No 111
Swastik Platinum
Dwarli
Thane 421306

WO Number : 4100017044

WO Document Dt : 21.08.2025

WO Creation Dt : 21.08.2025

IMPORTANT:

To report fraud or any ethical violation instance, log on to www.godrejspeakup.tip-offs.in or write anonymously to godrejspeakup@tip-offs.in or contact Whistleblowing Officer at ve.swaminathan@godrejinds.com or call 1800 309 3972.

ANNEXURE - 1

Vendor Address :

H N Power Solutions Private Limited
1st Floor
Shop No 111
Swastik Platinum
Dwarli
Thane 421306

WO No. : 4100017044

WO Date : 21.08.2025

Validity: 21.08.2025 To 21.04.2027

PAN No. : AAHCH3594E

PF No. : THTHA3290463000

EM No. : UDYAM-MH-33-0124969

V-GST No. : 27AAHCH3594E1ZF

Godrej Properties Limited

5TH FLOOR, GODREJ ONE,
PIROJSHANAGAR,
EASTERN,EXPRESS HIGHWAY,
VIKROLI EAST, Mumbai City,
Mumbai 400079
022-66510200
022-22072044
www.godrejproperties.com
GST No. : 27AAACG3995M1Z1

Sr. No.	B O Q	GST%	SAC/HSN	Qty	UOM	Unit Rate	Basic Value
1	ELECTRICAL PANELS						
1.1	SECTION - 1.0 ELECTRICAL PANELS "Design, Supply, Unloading, Handling, Shifting to Final Location, Reassembling, Installation, Testing & Commissioning of free standing, front operated, fully compartmentalized(From 3B, Type 2 cubical type, extendable on both sides Panel Boards suitable for indoor installation & for use on 415Volts 3-phase, 4wire, 50Hz system having (with-stand) fault current carrying capacity as specified, with suitable manual interlock arrangement, outgoing feeders, busbar & necessary metering with interconnections etc. Complete as per schematic drawing, Specification, relevant IS standards & including all accessories as per site conditions to make the system fully operational. Any sort of fabrication work required for erection of panel at site shall be done by the contractor. The contractor shall also check for all the loose joints and continuity of the panel. Any physical or technical defects envisaged by the contractor shall be brought to consultants and clients knowledge. All floor mounted panels shall be with 150mm height stand as per site condition. Note : Low Voltage switchgear shall comply to IS13032, IS13947, IEC61439 Panel shall be IEC61439 Approved All floor mounted panels shall be with 150mm height stand as per site condition. Approval of GA Drawing By Electrical Consultants/Client is must before fabrication.Refer SLD for details" Refer SLD for quoting TOWER PANEL	18.00	995411	1	NOS	628,500.00	628,500.00
1.2	Main Stack Parking Panel	18.00	995411	1	NOS	400,500.00	400,500.00
1.3	Stack Parking Panel-1 Lower Ground	18.00	995411	1	NOS	93,224.00	93,224.00
1.4	Stack Parking Panel-1-Ground	18.00	995411	1	NOS	149,500.00	149,500.00

ANNEXURE - 1

Vendor Address :

H N Power Solutions Private Limited
1st Floor
Shop No 111
Swastik Platinum
Dwarli
Thane 421306

WO No. : 4100017044

WO Date : 21.08.2025

Validity: 21.08.2025 To 21.04.2027

PAN No. : AAHCH3594E

PF No. : THTHA3290463000

EM No. : UDYAM-MH-33-0124969

V-GST No. : 27AAHCH3594E1ZF

Godrej Properties Limited

5TH FLOOR, GODREJ ONE,
PIROJSHANAGAR,
EASTERN,EXPRESS HIGHWAY,
VIKROLI EAST, Mumbai City,
Mumbai 400079
022-66510200
022-22072044
www.godrejproperties.com
GST No. : 27AAACG3995M1Z1

Sr. No.	B O Q	GST%	SAC/HSN	Qty	UOM	Unit Rate	Basic Value
1.5	Stack Parking Panel-2-Ground	18.00	995411	1	NOS	155,500.00	155,500.00
1.6	Stack Parking Panel-1 1st Floor-5th Floor	18.00	995411	5	NOS	158,500.00	792,500.00
1.7	Stack Parking Panel-2 1st Floor-5th Floor	18.00	995411	5	NOS	156,500.00	782,500.00
1.8	Unloading, Handling, Shifting to Final Location, Reassembling, Installation, Testing & Commissioning ACB/MCCB / MCB/BUSBAR BOX/TIMER with 16G MS powder coated enclosure, necessary busbar /spreader links, rotary handle etc complete. All MCCB upto and including 200 A shall be thermal magnetic adjustable and above 200 A shall be with microprocessor trip units. Only O/L AND S/C releases to be given. Approval of GA Drawing By Electrical Consultants/Client is must before fabrication. Supply, Unloading, Handling, Installation, Testing & Commissioning of surface mounted or mounted on iron angle frame- work, front operated Isolator in 1.6 mm thick MS powder coated enclosure. Complete as per schematic drawing, relevant standards & including all accessories as per site conditions to make the system fully operational. (Supply of only all switchgear (MCB,MCCB,RCCB WITH ENCLOSURE shall be in GPL scope however SITC of all required accessories shall be in contractor scope) 400 A FP MCCB 36kA with M.S. enclosure & busbar complete -	18.00	995411	3	NOS	1,600.00	4,800.00
1.9	63A FP RCCB 300mA with M.S. enclosure & busbar complete. (For Lift Motor & Lightning DB)	18.00	995411	3	NOS	370.00	1,110.00
1.10	40A FP RCCB 300mA with M.S. enclosure &	18.00	995411	2	NOS	370.00	740.00

ANNEXURE - 1

Vendor Address :

H N Power Solutions Private Limited
1st Floor
Shop No 111
Swastik Platinum
Dwarli
Thane 421306

WO No. : 4100017044

WO Date : 21.08.2025

Validity: 21.08.2025 To 21.04.2027

PAN No. : AAHCH3594E

PF No. : THTHA3290463000

EM No. : UDYAM-MH-33-0124969

V-GST No. : 27AAHCH3594E1ZF

Godrej Properties Limited

5TH FLOOR, GODREJ ONE,
PIROJSHANAGAR,
EASTERN,EXPRESS HIGHWAY,
VIKROLI EAST, Mumbai City,
Mumbai 400079
022-66510200
022-22072044
www.godrejproperties.com
GST No. : 27AAACG3995M1Z1

Sr. No.	B O Q	GST%	SAC/HSN	Qty	UOM	Unit Rate	Basic Value
	busbar complete. (For Lift Motor)						
1.11	16A DP RCCB 300mA with M.S. enclosure & busbar complete. (For Lift Light)	18.00	995411	3	NOS	270.00	810.00
1.12	32A FP MCB 10kA with M.S. enclosure & busbar complete.-(For Inverter)	18.00	995411	2	NOS	340.00	680.00
	Subtotal						3,010,364.00
2	CABLE TRAY						
2.1	CABLE TRAY Supply and Erecting Ladder type Hot dip G.I. cable tray of 2mm thickness of specific dimensions. The cable tray shall be hung from ceiling / fixed to wall with necessary ceiling suspensors, tee, flat sections, nuts etc, together with tees, bends etc including cost for supports as described. The tray shall be earthed. Min size (not a limitation) of supports shall be as follows (a).-up to 300mm tray 2nos. 8mm full threaded GI rod with 2nos.anchor fastener and "C" channel support at 500mm distance (b) 450 to 600mm tray 2nos.10mm full treaded GI rod with 2nos. anchor fastener and "C" channel support at 500mm distance (c) 750 / 1000 mm cable tray with fabrication of 25 x 6 mm angle frame with min. 4 nos anchor fastener at 500 mm distance. (Cable tray supports should be as per GPL SOP) 1200mm x 75mm	18.00	995411	30.00 0	RM	1,905.00	57,150.00
2.2	900mm x 75mm	18.00	995411	435.0 00	RM	1,220.00	530,700.00
2.3	600mm x75mm	18.00	995411	626.0 00	RM	985.00	616,610.00
2.4	450mm x75 mm	18.00	995411	477.0 00	RM	930.00	443,610.00
2.5	Supply and Erecting PERFORATED type Hot	18.00	995411	537.0	RM	1,195.00	641,715.00

ANNEXURE - 1

Vendor Address :

H N Power Solutions Private Limited
1st Floor
Shop No 111
Swastik Platinum
Dwarli
Thane 421306

WO No. : 4100017044

WO Date : 21.08.2025

Validity: 21.08.2025 To 21.04.2027

PAN No. : AAHCH3594E

PF No. : THTHA3290463000

EM No. : UDYAM-MH-33-0124969

V-GST No. : 27AAHCH3594E1ZF

Godrej Properties Limited

5TH FLOOR, GODREJ ONE,
PIROJSHANAGAR,
EASTERN,EXPRESS HIGHWAY,
VIKROLI EAST, Mumbai City,
Mumbai 400079
022-66510200
022-22072044
www.godrejproperties.com
GST No. : 27AAACG3995M1Z1

Sr. No.	B O Q	GST%	SAC/HSN	Qty	UOM	Unit Rate	Basic Value
	dip G.I. cable tray of 1.6mm thickness of specific dimensions. The cable tray shall be hung from ceiling / fixed to wall with necessary ceiling suspenders, tee, flat sections, nuts etc, together with tees, bends etc including cost for supports as described. The tray shall be earthed. Min size (not a limitation) of supports shall be as follows (a).-up to 300mm tray 2nos. 8mm full threaded GI rod with 2nos.anchor fastener and "C" channel support at 500mm distance (b) 450 to 600mm tray 2nos.10mm full treaded GI rod with 2nos. anchor fastener and "C" channel support at 500mm distance (c) 750 / 1000 mm cable tray with fabrication of 25 x 6 or 50 x 3 mm angle frame with min. 4 nos anchor fastener at 500 mm distance. 300mm X 75mm			00			
2.6	150mm X50mm	18.00	995411	336.00	RM	765.00	257,040.00
2.7	50mm X 50mm	18.00	995411	1,126.00	RM	525.00	591,150.00
	Subtotal						3,137,975.00
3	DISTRIBUTION BOARDS - FACTORY FABRICATED						
3.1	SECTION - 3.0 DISTRIBUTION BOARDS - FACTORY FABRICATED. " Unloading, Handling, Installation, Testing & Commissioning of Factory Fabricated (CRCA Sheet shall be of minimum 1.2mm thick) -(only Supply of all DB with internal switchgear shall be in GPL Scope however SITC of all required accessories shall be in contractor sope) Prewired, Distribution Board concealed in wall, surface mounted,front operated, suitable for use on 240/415Volts 1/3-phase, 3/4wire, 50Hz system, IP 43, IK 09 protection, complete with all accessories Like Busbars, Nuetrals Links, Earth Link, PPI Buslinks ,Cable End Box, Spreaders, Per Phase Isolation Kits, Blank plates,interconnections, connectors , Reversible Doors, Prefitted Masking Sheet,	18.00	995411	1	NOS	1,200.00	1,200.00

ANNEXURE - 1

Vendor Address :

H N Power Solutions Private Limited
1st Floor
Shop No 111
Swastik Platinum
Dwarli
Thane 421306

WO No. : 4100017044

WO Date : 21.08.2025

Validity: 21.08.2025 To 21.04.2027

PAN No. : AAHCH3594E

PF No. : THTHA3290463000

EM No. : UDYAM-MH-33-0124969

V-GST No. : 27AAHCH3594E1ZF

Godrej Properties Limited

5TH FLOOR, GODREJ ONE,
PIROJSHANAGAR,
EASTERN,EXPRESS HIGHWAY,
VIKROLI EAST, Mumbai City,
Mumbai 400079
022-66510200
022-22072044
www.godrejproperties.com
GST No. : 27AAACG3995M1Z1

Sr. No.	B O Q	GST%	SAC/HSN	Qty	UOM	Unit Rate	Basic Value
	Cable ties ,angle supports for Installations etc. Complete as per schematic drawing, relevant standards & including all accessories as per site conditions to make the system fully operational ,including Caution stickers 100 x 100 mm DB and Low Voltage switchgear shall comply to IS13032, IS13947, IEC61439 a) The MCB selection shown in DB Schedules to be based on the followings - B Curve MCB - for Lighting Load C Curve MCB - for Power Load D Curve MCB - for Motor Load The DB shall be double door type and vertical in fashion with width not more than 500 mm All the TPN DB shall be PPI type" VTPN DISTRIBUTION BOARD 4 way Vertical Distribution board with 32A FP MCB, 10kA as incomer and 3 nos. of 25A TP MCB 10kA & 3 nos of 25A SP MCB 10kA as outgoing.						
3.2	6 way Vertical Distribution board with 63A FP MCB, 10kA as incomer and 3 nos. of 25A TP MCB 10kA & 3 nos of 25A SP MCB 10kA as outgoing.	18.00	995411	1	NOS	1,400.00	1,400.00
3.3	8 way Vertical Distribution board with 32A FP MCB, 10kA as incomer and 3 nos. of 25A TP MCB 10kA & 3 nos of 25A SP MCB 10kA as outgoing.	18.00	995411	1	NOS	1,500.00	1,500.00
3.4	TPN DISTRIBUTION BOARD Supply installation testing and commissioning of 8 way Double door distribution board with 32A FP MCB 10kA as incomer 3nos. of 25A DP ELCB 30mA and 24 nos 6/10/16A SP MCB 10kA.	18.00	995411	6	NOS	1,400.00	8,400.00
3.5	Supply installation testing and commissioning of 6 way Double door distribution board with 32A FP MCB 10kA as incomer 3nos. of 25A DP ELCB 30mA and 18 nos 6/10/16A SP MCB 10kA.	18.00	995411	13	NOS	1,400.00	18,200.00

ANNEXURE - 1

Vendor Address :

H N Power Solutions Private Limited
1st Floor
Shop No 111
Swastik Platinum
Dwarli
Thane 421306

WO No. : 4100017044

WO Date : 21.08.2025

Validity: 21.08.2025 To 21.04.2027

PAN No. : AAHCH3594E

PF No. : THTHA3290463000

EM No. : UDYAM-MH-33-0124969

V-GST No. : 27AAHCH3594E1ZF

Godrej Properties Limited

5TH FLOOR, GODREJ ONE,
PIROJSHANAGAR,
EASTERN,EXPRESS HIGHWAY,
VIKROLI EAST, Mumbai City,
Mumbai 400079
022-66510200
022-22072044
www.godrejproperties.com
GST No. : 27AAACG3995M1Z1

Sr. No.	B O Q	GST%	SAC/HSN	Qty	UOM	Unit Rate	Basic Value
3.6	SPN DISTRIBUTION BOARD Supply, Installation testing and commissioning of 8 way SPN DB with 16 A DP RCBO 30mA as incomer 6 nos 10A SP MCB 10kA as outgoing..	18.00	995411	5	NOS	1,200.00	6,000.00
3.7	Supply, Installation testing and commissioning of 6 way SPN DB with 16 A DP RCBO 30mA as incomer 6 nos 10A SP MCB 10kA as outgoing..	18.00	995411	8	NOS	1,200.00	9,600.00
3.8	Supply, Installation testing and commissioning of 4 way SPN DB with 16 A DP RCBO 30mA as incomer 6 nos 10A SP MCB 10kA as outgoing..	18.00	995411	5	NOS	1,200.00	6,000.00
Subtotal							52,300.00
4	CABLES						
4.1	SECTION - 4.0 CABLES Supply, Laying, testing and commissioning of cables as per IS : 694 & IS : 5831 on cable trays, structural supports and cable supports provided, include unloading, shifting upto site. The scope includes clamping of cables by ready made G.I. spacers, saddles or clamps fabricated out of M.S. strip 3 mm thick, Treasing and Clamping of Cable on cable tray, supply of all clamping materials and hardware etc., providing cable tags made out of aluminium strip and 75x20 mm in size with cable number and size punched on it. Cable tags shall be tied to cables at every 20 meter interval and at both the ends. Supports provided for clamping of cables upto individual motors and push-buttons shall be included be paid extra as per item rate for MS fabrication work. Empty cable drums shall be returned to stores. In case of laying unlisted cables, rate of cable whose outer dia is closest to the cable sizes quoted shall be applicable. The same shall hold good for	18.00	995411	20.30 0	RM	1,590.00	32,277.00

ANNEXURE - 1

Vendor Address :

H N Power Solutions Private Limited
1st Floor
Shop No 111
Swastik Platinum
Dwarli
Thane 421306

WO No. : 4100017044

WO Date : 21.08.2025

Validity: 21.08.2025 To 21.04.2027

PAN No. : AAHCH3594E

PF No. : THTHA3290463000

EM No. : UDYAM-MH-33-0124969

V-GST No. : 27AAHCH3594E1ZF

Godrej Properties Limited

5TH FLOOR, GODREJ ONE,
PIROJSHANAGAR,
EASTERN,EXPRESS HIGHWAY,
VIKROLI EAST, Mumbai City,
Mumbai 400079
022-66510200
022-22072044
www.godrejproperties.com
GST No. : 27AAACG3995M1Z1

Sr. No.	B O Q	GST%	SAC/HSN	Qty	UOM	Unit Rate	Basic Value
	cable termination also. FRLS armoured Cables						
	3.5 core 300 sq. mm						
4.2	3.5 core 185 sq. mm.	18.00	995411	100.00	RM	1,010.00	101,000.00
4.3	3.5 core 150 sq. mm	18.00	995411	85.00	RM	860.00	73,100.00
4.4	3.5 core 35 sq. mm-AL	18.00	995411	111.00	RM	245.00	27,195.00
4.5	3.5 core 25 sq. mm-AL	18.00	995411	150.00	RM	235.00	35,250.00
4.6	4 core 16 sq. mm	18.00	995411	149.00	RM	195.00	29,055.00
4.7	4 core 6 sq. mm -Cu	18.00	995411	618.00	RM	387.00	239,166.00
4.8	3 core 4 sq.mm copper cable	18.00	995411	396.00	RM	230.00	91,080.00
4.9	4 core 2.5 sq.mm copper cable	18.00	995411	19,247.00	RM	202.50	3,897,517.50
4.10	4 core 4 sq.mm copper FS cable	18.00	995411	80.00	RM	343.00	27,440.00
	Subtotal						4,553,080.50
5	CABLE TERMINATION						
5.1	SECTION - 5.0 CABLE TERMINATION Supply & Fixing Double compression Glands(Above & incl. 150 Sq.mm)/ Single compression Glands(till 150 Sq.mm) Brass glands & making joint with necessary AL./CU. crimping socket(As per Cable MOC) of long neck type connecting the same to various equipment like section pillar, switch, starter, motor etc. for the following sizes Crimping shall be done with use of Hydraulic Crimping tool only. Cost to include for stripping of cable insulation, supply and fixing of lugs, armour	18.00	995411	2	NOS	2,980.00	5,960.00

ANNEXURE - 1

Vendor Address :
H N Power Solutions Private Limited
1st Floor
Shop No 111
Swastik Platinum
Dwarli
Thane 421306

WO No. : 4100017044
WO Date : 21.08.2025
Validity: 21.08.2025 To 21.04.2027
PAN No. : AAHCH3594E
PF No. : THTHA3290463000
EM No. : UDYAM-MH-33-0124969
V-GST No. : 27AAHCH3594E1ZF

Godrej Properties Limited
5TH FLOOR, GODREJ ONE,
PIROJSHANAGAR,
EASTERN,EXPRESS HIGHWAY,
VIKROLI EAST, Mumbai City,
Mumbai 400079
022-66510200
022-22072044
www.godrejproperties.com
GST No. : 27AAACG3995M1Z1

Sr. No.	B O Q	GST%	SAC/HSN	Qty	UOM	Unit Rate	Basic Value
	earthing and hydraulic crimping . Fixing of cable glands with banzel clip connected to earth. FRLS Cables 3.5 core 300 sq. mm						
5.2	3.5 core 185 sq. mm.	18.00	995411	4	NOS	2,063.75	8,255.00
5.3	3.5 core 150 sq. mm	18.00	995411	2	NOS	1,949.50	3,899.00
5.4	4 core 35 sq. mm	18.00	995411	10	NOS	672.50	6,725.00
5.5	3.5 core 25 sq. mm-AL	18.00	995411	14	NOS	657.75	9,208.50
5.6	4 core 16 sq. mm	18.00	995411	10	NOS	589.00	5,890.00
5.7	4 core 6 sq. mm -Cu	18.00	995411	22	NOS	515.00	11,330.00
5.8	3 core 4 sq.mm copper cable	18.00	995411	10	NOS	430.00	4,300.00
5.9	4 core 4 sq.mm copper cable	18.00	995411	730	NOS	390.00	284,700.00
5.10	4 core 4 sq.mm copper FS cable	18.00	995411	8	NOS	390.00	3,120.00
	Subtotal						343,387.50
6	POINT WIRING & CONDUITING						
6.1	SECTION - 6.0 POINT WIRING & CONDUITING "Point wiring shall be done with supply, installation, testing and commissioning of FRLS category 3R x 1.5sqmm cu FRLS wires from modular switches to Primary light point & 3R x 1.5sqmm cu FRLS wires from Primary Light point to Secondary Light Point in existing FR PVC MMS HMS conduit.(Mains of 3 Nosx1.5 Sqmm Wire from	18.00	995411	176	NOS	3,530.00	621,280.00

ANNEXURE - 1

Vendor Address :

H N Power Solutions Private Limited
1st Floor
Shop No 111
Swastik Platinum
Dwarli
Thane 421306

WO No. : 4100017044

WO Date : 21.08.2025

Validity: 21.08.2025 To 21.04.2027

PAN No. : AAHCH3594E

PF No. : THTHA3290463000

EM No. : UDYAM-MH-33-0124969

V-GST No. : 27AAHCH3594E1ZF

Godrej Properties Limited

5TH FLOOR, GODREJ ONE,
PIROJSHANAGAR,
EASTERN,EXPRESS HIGHWAY,
VIKROLI EAST, Mumbai City,
Mumbai 400079
022-66510200
022-22072044
www.godrejproperties.com
GST No. : 27AAACG3995M1Z1

Sr. No.	B O Q	GST%	SAC/HSN	Qty	UOM	Unit Rate	Basic Value
	DB to SB & SB TO SB For Lighting Circuit , Mains of 3Nosx2.5 Sqmm wire from DB TO SB & SB TO SB For Power point shall be part of point Rate) Also 3 x 2.5 sq.mm.earth (for points 6Amps & 16Amps) & with 3 x 4 sq.mm wires (for 20Amps) shall be from Distribution Boards in suitable size of PVC conduits. SITC of switches, sockets, regulators, blank plates, front plates, switchboard etc are part of the point rate. All wire ends shall be lugged properly and ferruled at both D.B. and S.B. end. All wire sizes unless specified below shall be as per specifications. Slotted angle cum threaded rods ,Back plate/wooden frame in mivan/dry wall structure shall be used for main path of conduiting through corridors which is deemed to be included in rates quoted. as per architect's approval. Earth wire shall be one size smaller than the phase wire - limited to min. size of 1.5 sqmm. The cost shall also be inclusive of Accessories like Faceplates/Ceiling rose, Batten / Angle Holder/ Hooks/ Box/ Clamps and Other necessary accessories for completing the installation in Mivan/dry wall / Brick wall / block work etc. complete to the satisfaction of engineer incharge. -1.2mm thick GI Box, constructed out of 120 GSM, Pre-Galvanized MS sheets as per technical specifications and approved make list with 2 coats of Zinc Chromate to be applied on boxes at site before installation. -All the Fittings and accessories shall comply to relevant latest IS standards -""FRLS"" wires shall comply to IS 694:1990 / IEC 60227-1 to 5:1979 -Rigid PVC conduit Conduits and accessories complying to IS 9537(Part 1):1980/ IEC 60614-1(1978) -Plugs and Socket shall comply to : IS 1293:2005 / IEC 60884-1 (2002) -Switch And Sockets shall comply to : IS 3854:1997 / IEC 60669-1(1998) -Ceiling Rose Shall comply to : IS 371:1999 " Only Switch , Socket & Blank plate Shall be Supply is in GPL Scope Parking Area						

ANNEXURE - 1

Vendor Address :

H N Power Solutions Private Limited
1st Floor
Shop No 111
Swastik Platinum
Dwarli
Thane 421306

WO No. : 4100017044

WO Date : 21.08.2025

Validity: 21.08.2025 To 21.04.2027

PAN No. : AAHCH3594E

PF No. : THTHA3290463000

EM No. : UDYAM-MH-33-0124969

V-GST No. : 27AAHCH3594E1ZF

Godrej Properties Limited

5TH FLOOR, GODREJ ONE,
PIROJSHANAGAR,
EASTERN,EXPRESS HIGHWAY,
VIKROLI EAST, Mumbai City,
Mumbai 400079
022-66510200
022-22072044
www.godrejproperties.com
GST No. : 27AAACG3995M1Z1

Sr. No.	B O Q	GST%	SAC/HSN	Qty	UOM	Unit Rate	Basic Value
	Emg Light point controlled by MCB directly with 3runs 1.5sqmmcu flexible wires. Cost of MCB is not part of this item. (Primary) Avg Lengh-30 meter						
6.2	Emg Light point controlled lopped from above with 3runs 1.5sqmm cu flexible wires.(Secondary) Avg Lengh-10 meter	18.00	995411	1,028	NOS	1,230.00	1,264,440.00
6.3	LIFT LOBBY, REFUGE AREA, TERRACE FLOOR, METER ROOM PANEL ROOM,STAIRCASE AREA Light point controlled by MCB directly with 3runs 1.5sqmm cu flexible wires. Cost of MCB is not part of this item. (Primary) Avg Lengh-8 meter	18.00	995411	25	NOS	982.30	24,557.50
6.4	Light point controlled looped from above point with 3runs 1.5sqmm cu flexible wires. Cost of MCB is not part of this item.(Secondary) Avg Lengh-5 meter	18.00	995411	125	NOS	615.00	76,875.00
6.5	Light point controlled by one single way 6 A switch with 3runs 1.5sqmm cu flexible wires.(Primary) Avg Lengh-8 meter	18.00	995411	9	NOS	982.30	8,840.70
6.6	Light point controlled by lopped from above with 3runs 1.5sqmm cu flexible wires.(Secondary) Avg Lengh-5 meter	18.00	995411	61	NOS	615.00	37,515.00
6.7	6 A x 230 Volt 3 pin socket outlet point controlled by 6 A switch at onboard including box plate etc complete to be done 3runs 2.5sqmm cu flexible wires from existing lighting circuit Avg Lengh-30 meter	18.00	995411	83	NOS	3,720.00	308,760.00
6.8	6 A x 230 Volt 3 pin socket outlet point controlled Looped to be done 3runs 2.5sqmm cu flexible wires from existing lighting circuit Avg Lengh-18 meter	18.00	995411	84	NOS	3,040.00	255,360.00
6.9	LIFT SHAFT Lift shaft board with 1 nos. 6A Socket+Switch/Lamp Holder & 6A switch for Lamp with 3C X 2.5 Armoured Copper Cable.Avg Lengh-15 meter	18.00	995411	5	NOS	2,398.46	11,992.30

ANNEXURE - 1

Vendor Address :

H N Power Solutions Private Limited
1st Floor
Shop No 111
Swastik Platinum
Dwarli
Thane 421306

WO No. : 4100017044

WO Date : 21.08.2025

Validity: 21.08.2025 To 21.04.2027

PAN No. : AAHCH3594E

PF No. : THTHA3290463000

EM No. : UDYAM-MH-33-0124969

V-GST No. : 27AAHCH3594E1ZF

Godrej Properties Limited

5TH FLOOR, GODREJ ONE,
PIROJSHANAGAR,
EASTERN,EXPRESS HIGHWAY,
VIKROLI EAST, Mumbai City,
Mumbai 400079
022-66510200
022-22072044
www.godrejproperties.com
GST No. : 27AAACG3995M1Z1

Sr. No.	B O Q	GST%	SAC/HSN	Qty	UOM	Unit Rate	Basic Value
6.10	-do- as 6.4.1 above but looped from above socket with 3C X 2.5 Armoured Copper Cable. Avg Lenght-7 meter	18.00	995411	35	NOS	1,308.00	45,780.00
6.11	CONDUITS Providing and laying of I.S.I. mark GI conduit as per with all necessary accessories like junction/pull boxes, G.I fish wire, fixing accessories etc as required. The rates shall include chasing of walls, floors etc & plastering the chased portion, if required, however, HDGI conduits shall be used for surface mounted applications like in Electrical shafts, ELV shafts, Lift shafts, et.c (For open wiring) 25mm dia	18.00	995411	200.00	RM	245.00	49,000.00
	Subtotal						2,704,400.50
7	LIGHT FIXTURES & FANS						
7.1	SECTION -7.0 LIGHT FIXTURES & FANS : "Unloading,Installation, testing & commissioning of standard light fittings and lighting accessories including lamp Ballast, Controller,Internal wiring. The scope shall include, providing of all hardware such as nuts,anchor fasteners, bolts, screws, cleats, clamps, PVC insulated wires / cables from Junction box to lighting fixtures, ball and socket 'arrangement with J.B., suspension conduit pipe for drop for fluorescent fitting The cost of fabrication and installation of MS supports will be paid extra as per rates quoted elsewhere. All fixtures shall be with Electronic ballasts of APFC type.Fan Outlet Shall be provided with Minimum 600mm Long Fanrod and Accessories like Bushing, Nut bolts , Clips, Pin Etc. (Only Supply of Light Fixture shall GPL Scope however all Required accessories for installation shall be in contractor scope)" 9 watt Bulk head light with fitting - LIFT SHAFT	18.00	995411	40	NOS	160.00	6,400.00
7.2	9W Ramp LIGHT	18.00	995411	95	NOS	160.00	15,200.00

ANNEXURE - 1

Vendor Address :

H N Power Solutions Private Limited
1st Floor
Shop No 111
Swastik Platinum
Dwarli
Thane 421306

WO No. : 4100017044

WO Date : 21.08.2025

Validity: 21.08.2025 To 21.04.2027

PAN No. : AAHCH3594E

PF No. : THTHA3290463000

EM No. : UDYAM-MH-33-0124969

V-GST No. : 27AAHCH3594E1ZF

Godrej Properties Limited

5TH FLOOR, GODREJ ONE,
PIROJSHANAGAR,
EASTERN,EXPRESS HIGHWAY,
VIKROLI EAST, Mumbai City,
Mumbai 400079
022-66510200
022-22072044
www.godrejproperties.com
GST No. : 27AAACG3995M1Z1

Sr. No.	B O Q	GST%	SAC/HSN	Qty	UOM	Unit Rate	Basic Value
7.3	9W CEILING DOWN LIGHT	18.00	995411	21	NOS	160.00	3,360.00
7.4	20W LED TUBE LIGHT-FOR STAIRCASE,Praking AREA,panel room	18.00	995411	1,308	NOS	150.00	196,200.00
	Subtotal						221,160.00
8	UPS/ INVERTER WORKS						
8.1	SECTION -8.0 UPS/ INVERTER WORKS Supply, Installation, testing and commissioning of 10 KVA INVERTER, Three phase input and Three phase output IGBT based with 0.9 output p.f. & 15 minutes battery back up With SMF Batteries. - For Emergency Lighting	18.00	995411	1	NOS	198,125.00	198,125.00
	Subtotal						198,125.00
9	EARTHING						
9.1	SECTION 9.0 - EARTHING "Supply & making of Earthing station with the use of 32mm dia. copper bonded rod, 3 mtr long and filling of 50 kg of compound complete with chamber, lid cover and tap off & test point. Cost shall be inclusive of masonry chamber 450x 450 mm with masonry base, CI chequered plate manhole cover with frame and bitumastic paint with digging of pit upto permanent misture level but not less than 3 metres and back filling as required. and as per IS 3043. to achieve Minimum 2.5 Ohms. Note: The Qty indicated are indicative only. Contractor to submit the calulation and augment the number of earthpits required to achieve Resistance values of less than 2.5 Ohms. The earthing sytem installation shall be certified by Original Equipment Manufacturer and warranty of minimum 5 years shall be obtained duly certitifed by original equipment manufacturer and submitted to the client."	18.00	995411	2	NOS	20,500.00	41,000.00

ANNEXURE - 1

Vendor Address :
H N Power Solutions Private Limited
1st Floor
Shop No 111
Swastik Platinum
Dwarli
Thane 421306

WO No. : 4100017044
WO Date : 21.08.2025
Validity: 21.08.2025 To 21.04.2027
PAN No. : AAHCH3594E
PF No. : THTHA3290463000
EM No. : UDYAM-MH-33-0124969
V-GST No. : 27AAHCH3594E1ZF

Godrej Properties Limited
5TH FLOOR, GODREJ ONE,
PIROJSHANAGAR,
EASTERN,EXPRESS HIGHWAY,
VIKROLI EAST, Mumbai City,
Mumbai 400079
022-66510200
022-22072044
www.godrejproperties.com
GST No. : 27AAACG3995M1Z1

Sr. No.	B O Q	GST%	SAC/HSN	Qty	UOM	Unit Rate	Basic Value
9.2	"Supply & making of Earthing station with the use of 32mm dia. GI rod, 3 mtr long and filling of 50 kg of compound complete with chamber, lid cover and tap off & test point. Cost shall be inclusive of masonry chamber 450x 450 mm with masonry base, CI chequered plate manhole cover with frame and bitumastic paint with digging of pit upto permanent misture level but not less than 3 metres and back filling as required. and as per IS 3043. to achieve Minimum 2.5 Ohms. Note: The Qty indicated are indicative only. Contractor to submit the calulation and augment the number of earthpits required to achieve Resistance values of less than 2.5 Ohms. The earthing sytem installation shall be certified by Original Equipment Manufacturer and warranty of minimum 5 years shall be obtained duly certitified by original equipment manufacturer and submitted to the client."	18.00	995411	16	NOS	11,500.00	184,000.00
9.3	Supply and Laying Cu./GI. earthing strips for interconnecting the earthing stations, panels, DB's etc. in built-up trenches, on walls/ceiling, buried in ground generally as specified and shown on drawings complete with : 50X6 CU STRIP	18.00	995411	53.00 0	RM	2,322.00	123,066.00
9.4	50X6 GI STRIP	18.00	995411	53.00 0	RM	378.10	20,039.30
9.5	25X3 GI STRIP	18.00	995411	460.0 00	RM	106.40	48,944.00
9.6	25X6 GI STRIP	18.00	995411	50.00 0	RM	201.60	10,080.00
9.7	8SWG GI WIRE	18.00	995411	2,500. 000	RM	31.00	77,500.00
9.8	Equipotential bars Equipotential bars - 300 x 50 x 6 mm GI IN PANEL ROOM	18.00	995411	2	NOS	780.00	1,560.00

ANNEXURE - 1

Vendor Address :

H N Power Solutions Private Limited
1st Floor
Shop No 111
Swastik Platinum
Dwarli
Thane 421306

WO No. : 4100017044

WO Date : 21.08.2025

Validity: 21.08.2025 To 21.04.2027

PAN No. : AAHCH3594E

PF No. : THTHA3290463000

EM No. : UDYAM-MH-33-0124969

V-GST No. : 27AAHCH3594E1ZF

Godrej Properties Limited

5TH FLOOR, GODREJ ONE,
PIROJSHANAGAR,
EASTERN,EXPRESS HIGHWAY,
VIKROLI EAST, Mumbai City,
Mumbai 400079
022-66510200
022-22072044
www.godrejproperties.com
GST No. : 27AAACG3995M1Z1

Sr. No.	B O Q	GST%	SAC/HSN	Qty	UOM	Unit Rate	Basic Value
9.9	Equipotential bars - 300 x 25 x 6 mm GI IN ELECTRICAL SHAFT	18.00	995411	2	NOS	650.00	1,300.00
9.10	Equipotential bars - 150 x 50 x 3 mm GI. LIFT SHAFT	18.00	995411	5	NOS	560.00	2,800.00
9.11	Equipotential bars - 300 x 25 x 6 mm CU. ELV ROOM	18.00	995411	1	NOS	1,170.00	1,170.00
	Subtotal						511,459.30

ANNEXURE - 2

Vendor Address :

H N Power Solutions Private Limited
1st Floor
Shop No 111
Swastik Platinum
Dwarli
Thane 421306

WO No. : 4100017044**WO Date :** 21.08.2025**Validity:** 21.08.2025 To 21.04.2027**PAN No. :** AAHCH3594E**PF No. :** THTHA3290463000**EM No. :** UDYAM-MH-33-0124969**V-GST No. :** 27AAHCH3594E1ZF**Godrej Properties Limited**

5TH FLOOR, GODREJ ONE,
PIROJSHANAGAR,
EASTERN,EXPRESS HIGHWAY,
VIKROLI EAST, Mumbai City,
Mumbai 400079
022-66510200
022-22072044
www.godrejproperties.com
GST No. : 27AAACG3995M1Z1

Terms & Conditions

1. Performance Bank Guarantee

Contractor shall provide, within 15 days of receipt of Notice to Proceed, a performance deposit of an amount equivalent to 5% of the Contract Amount in a manner specified in the GCC. This Performance Deposit shall be in the form a Bank Guarantee from a Nationalized Indian Bank valid up to Contract Period + 90 days or in the form of cash retention of equivalent amount from initial 8 RA bills.

2.Defects Liability Period # Defects Liability Period shall be 24 Months from the date of issue of Virtual Completion Certificate (VCC).

3. Deposit against DLP: - 5% (Five percent) of each running account bill shall be deposited towards the deposit against DLP services. Contractor to refer GCC for detailed terms.

OR-Contractor may submit Bank Guarantee at start of work for 5% of Contract value, valid till completion of DLP. No deduction shall be made in RA bills.

OR-Contractor may submit Bank Guarantee on completion of work for 5% of Contract value, valid till completion of DLP. Deducted amount against RA bill shall be released on submission of BG.

4. Payment Terms and Conditions:

Contractor to raise RA bills on from 1st to 5th of every month. RA bills shall be paid within 30 days after submission of commercially correct tax invoice.

Note: - All Requisite documents as per GPL Standards shall be enclosed with Proforma Invoice & Tax Invoice.

For Point Wiring Items:

1. 20% on Completion of Slab conduiting Works on pro rata basis.
2. 15% on completion of wall conduiting, back box fixing & rope pulling on pro rata basis.
3. 30% on Supply of wiring on pro rata basis.
4. 10% on installation of wiring on pro rata basis.
5. 15% on installation of Switch, Socket, Plate etc on pro rata basis.
6. 05% on testing and commissioning on pro rata basis.
7. 05% on complete handover to the company

For Cables, trays & all other material where supply (M + L) is in contractor's scope :-

- 70% of item rate after supply of material on pro rata basis.
- 20% of item rate after installation on pro rata basis.
- 5% of item rate after testing & commissioning on pro rata basis.
- 5% after complete handover to the company.

For free issue material such as Lights which are free issue by Company :-

- 90% of Item Rate after installation of works on pro rata basis.
- 5% of Item Rate against testing & commissioning on pro rata basis.
- 5% of Item Rate after complete handover to the Company.

For DBs with enclosure where material is free issue by Company :-

- 60% of Item Rate after DB Enclosure installation works incl. wall finishing (as per EIC) on pro rata basis.
- 30% of Item Rate after installation of MCB/switchgears and DB Dressing works on pro rata basis.
- 05% of Item Rate against testing & commissioning on pro rata basis.

ANNEXURE - 2

Vendor Address :

H N Power Solutions Private Limited
1st Floor
Shop No 111
Swastik Platinum
Dwarli
Thane 421306

WO No. : 4100017044**WO Date :** 21.08.2025**Validity:** 21.08.2025 To 21.04.2027**PAN No. :** AAHCH3594E**PF No. :** THTHA3290463000**EM No. :** UDYAM-MH-33-0124969**V-GST No. :** 27AAHCH3594E1ZF**Godrej Properties Limited**

5TH FLOOR, GODREJ ONE,
PIROJSHANAGAR,
EASTERN,EXPRESS HIGHWAY,
VIKROLI EAST, Mumbai City,
Mumbai 400079
022-66510200
022-22072044
www.godrejproperties.com
GST No. : 27AAACG3995M1Z1

Terms & Conditions

-05% of Item Rate after complete handover to the Company

5. Power & Water - Construction + Drinking Water & Construction Power shall be in Company's scope & shall be available at every alternate floor in the building. Further distribution shall be done by the Contractor at his own cost.
6. Labour Accommodation - Readymade Labour accommodation i.e. Labour accommodation facilities shall be arranged by the company free of cost; however, Rs. 500 per month per labour will be charged as a maintenance cost for regular housekeeping and toilet sanitation. Food waste disposal will be the contractor's responsibility. Note: - Labour accommodation will be provided based on availability at the site. In case labour accommodation is not available on-site, the contractor shall arrange alternative accommodation outside of the premises at their own cost.
7. Storage space: Only space will be provided at site for material storage, all necessary lock and key and facility development and security will be in scope of the Contractor.
8. Building Configuration- MLCP (Pump Room+LB+G+5) All Floor Heights explained during Tendering
9. Facilities by the Company:
 - a.Sanitation Facilities including maintenance.
 - b.Space for Storages, Site offices.
 - c.Labour Hutments. However, Maintenance of labour camp & Daily garbage disposal by the Contractor.
 - d.Quality Park, Safety Park, Medical Ambulance, Doctors visit twice a week, First Aid, Induction room and all associated amenities.
10. Contract Period: 20 Months (including mobilization period of 15 days & final billing period of 3 months)
11. Local management and Mathadi # Local handling shall be in GPL scope however, unloading & Mathadi charges for free issue material & contractor material shall be in contractor scope.
12. Contractor should deploy Safety officer (ADIS) as per GPL norms & qualified engineer.
13. Free Issue material : All Distribution Boards, MCB, RCCB, MCCB with Enclosure, light Fixtures etc. Rest of the Materials shall be in the Contractor scope.
Unloading, Mathadi and Varai charges of all Free Issue Materials & Contractor Material will be in the scope of Contractor.
14. Basic Rate Items: Cables, Wires. Rest all material will be in the contractor's scope.
GPL has provided basic rates for Cables, Wires along with tender documents.
Successful Contractor need to approve these rates from GPL prior to material order. Also note that, escalation on basic rates shall be applied on certified quantities only. Escalation shall not be applicable on material wastage part as well any overheads. The variance will be given only on the difference of basic rate against market rates at the time of order
15. Protective covering for all type of piping/equipment's/accessories during execution of work shall be done by contractor at his own cost.
16. Contractor should use Mobile scaffold with all wheels are locked for work in MLCP area.
17. For Zurry work, conduiting should done by machineries instructed by site team, Filling of zurry by RMP and fixing of fibre chicken mesh as per approved make, DB fixing and filling by material approved by Quality should be in scope of

ANNEXURE - 2

Vendor Address :

H N Power Solutions Private Limited
1st Floor
Shop No 111
Swastik Platinum
Dwarli
Thane 421306

WO No. : 4100017044
WO Date : 21.08.2025
Validity: 21.08.2025 To 21.04.2027
PAN No. : AAHCH3594E
PF No. : THTHA3290463000
EM No. : UDYAM-MH-33-0124969
V-GST No. : 27AAHCH3594E1ZF

Godrej Properties Limited
5TH FLOOR, GODREJ ONE,
PIROJSHANAGAR,
EASTERN,EXPRESS HIGHWAY,
VIKHROLI EAST, Mumbai City,
Mumbai 400079
022-66510200
022-22072044
www.godrejproperties.com
GST No. : 27AAACG3995M1Z1

Terms & Conditions

contractor including (L+M)

18. Material Wastages for Free Issue Materials shall be NIL.

19. Contractor are agreed for Electrical Work Execution as per availability of work front at site for MLCP to achieve slab cycle within schedule. No continues work front will be available for MLCP conduiting work.

20. Quality Compliance & Penalty Clauses:

- Contractor to comply to all Quality requirements as per Tender document/SOP
- All Penalty clauses related to Resources & Work Shall be as per Penalty matrix. NCs shall be closed within 7 days of issuance.

21. Labour Compliance: All Labour Compliance to be followed as per regulatory construction norms & as per GPL standards. No deviation would be accepted.

22. Rates are inclusive as per GPL Technical specifications, list of makes and Tender drawings provided. Unit rates are firm & fixes throughout the contract period. No change in rates will be accepted until change in tender documents.

23. Quantities set out in the BOQ are approximate quantities for the Works, basis the tender drawings and are not to be construed as the actual and correct quantities for the Works to be executed. The Contractor is required to estimate the quantities as per the approved (GFC drawings) and/ or instructions issued by the Company from time to time. It is the obligation of the Contractor to inform the Company of any variations in the quantities of BOQ item/(s) or any extra item/(s) not provided for in the BOQ. The Contractor shall submit Cost to complete (CTC) including but not limited to any revised quantities, extra items for the entire scope of works as per the latest GFC drawings and/or instructions issued by the Company within 10 Days of issuance from time to time to the Company's Project Manager.